



Request for Proposal For

E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK -BRANCH OFFICE-RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH- RASRA DIST- BALIA UP-221712

E-TENDER REFERENCE NO: - PSB/ROVNS/PREMISES/TENDER/02/2026-27

Date of issue of E-Tender	20.04.2026
Bid Submission Start Date	20.04.2026 by 11:00 AM
Pre- Bid Meeting Date	21.04.2026 at 11:00 AM
Bid Submission End Date	04.05.2026 up to 05:00 PM
Technical bid opening date	05.05.2026 at 11:00 AM
Financial Bid Opening date	Will be informed subsequently to technically qualified bidders on Psb eproc

**PUNJAB AND SIND BANK,
REGIONAL OFFICE VARANASI,
SECOND FLOOR SH-15/182-M-A-2, AIRPORT ROAD, SHIVPUR, DISTT.
VARANASI-221003**

ARCHITECT:

**M/S Vaastu Vikalp Architects
S-24, First Floor S2S Square,
Garh Road, Meerut -250002
Mobile – 9899328602,9997591118**

Local Add- Ratwarbegpur, post- Kanakpur, near Pindra Railway station, Varanasi-221206

E-Tender Document

E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH OFFICE-RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH- RASRA DIST- BALIA UP-221712

Bid Submission Start Date : 20.04.2026 by 11:00 AM

Pre-Bid meeting Date : 21.04.2026 at 11:00 AM

Last date of Submission of Tender : 04.05.2026 up to 05:00 PM

Technical bid opening date : 05.05.2026 at 11:00 AM

Financial Bid Opening date : Will be informed subsequently to technically qualified Bidder on Psb eproc

Time of Completion of the Project : 30 days

The information provided by the bidders in response to this RFP Document will become the property of the Bank and will not be returned. The Bank reserves the right to amend, rescind or reissue this RFP Document and all amendments will be advised to the bidders and such amendments will be binding on them. The Bank also reserves its right to accept or reject any or all the responses to this RFP Document without assigning any reason whatsoever and without any cost or compensation therefor.

Disclaimer

While the document has been prepared in good faith, no representation or warranty, express or implied, is or will be made, and no responsibility or liability will be accepted by Punjab and Sind Bank or any of its employees, in relation to the accuracy or completeness of this document and any liability thereof expressly disclaimed. The RFP is not an offer by Punjab and Sind Bank, but an invitation for bidder's responses. No contractual obligation on behalf of Punjab and Sind Bank, whatsoever, shall arise from the offer process unless and until a formal contract is signed and executed by duly authorized officials of Punjab and Sind Bank and the selected Bidder.

**E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR
CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH
OFFICE-RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA
LAKHNESHWAR TEH- RASRA DIST- BALIA UP-221712**

E-Tender reference	PSB/ROVNS/PREMISES/TENDER/02/2026-27
Date of issue of RFP (Request for Proposal)	20.04.2026
Earnest money deposit	<p>Earnest money deposit of Rs.110000.00/- (EMD (Refundable) in the Account Number:-17325040070003 Name of Account:- NEFT INWARD STP PARKING ACCOUNT IFSC-PSIB0021732 BRANCH : TARNA BAZAR Varanasi OR Demand Draft (DD) in Favor of “ Punjab And Sind Bank, REGIONAL office Varanasi ”</p> <p>#All MSEs having registration as per provisions of the Public Procurement Policy for Micro and Small Enterprises i.e. District Industries Centre (DIC) or Khadi and Village Industries Commission (KVIC) or Khadi and Industries Board (KVIB) or Coir Board or National Small Industries Commission (NSIC) or directorate of Handicrafts and Handlooms or Udyog Aadhaar Memorandum or any other body specified by Ministry of MSME and Start-ups (recognized by DIPP) are exempted from submission of Tender Fee and Bid security declaration only. Relevant certificates should be submitted by the bidder in this Regard to avail exemption.</p>
Performance security	The amount of Performance security shall be @ 5% of the contract Price denominated in Indian Rupees
Last date & time of receipts of tender bids	04.05.2026 up to 05:00 p.m.
Liquidated damages for non-completion in time	1.0% of the contract value per week subject to a max of 10% of the contract value
Opening of Commercial/price bid	Only Eligible Tenderer shall be informed separately
Address of communication	‘Punjab and Sind Bank’, SECOND FLOOR SH-15/182-M-A-2,AIRPORT ROAD, SHIVPUR ,DISTT. VARANASI, VARANASI-221003
Email address	Ro.varanasi@psb.bank.in <u>mohit.saxena@psb.bank.in</u> ; <u>reeshoo.mishra@psb.bank.in</u>
Contact Telephone	Name: Mohit Saxena Designation: Chief Manager Phone No: 7837671366 Name: REESHOO KUMAR MISHRA Designation: Manager Phone No: 8299755730

Bids to be submitted	https://psb.eproc.in (Bidder has to submit the bid electronically)
Bid Validity Period	3 Months

Information for online participation

This Tender will follow e-tendering process which will be conducted by bank's authorized e-tendering services provider **M/s C1 India Pvt. Ltd.** through website: **<https://psb.eproc.in>**

Following activities will be conducted online through the above website

1. Procurement of RFP documents including all Annexures
2. Addendums to the RFP
3. Submission of technical bid & indicative commercial bid by the Bidder
3. Opening of technical bid & Indicative commercial bid by the bank
4. Reverse Auction
5. Announcement of result if any

Instructions:

1. Bidders who wish to participate will have to register with the website. (<https://psb.eproc.in>). Bidders will be required to create login id & password on their own in registration process.
2. Bidder who wish to participate in this tender need to procure Class-III Digital Signature Certificate (With Both DSC Components, i.e. Signing & Encryption) from any of the licensed Certifying Agency. Bidders can view the list of licensed CA.s from www.cca.gov.in.
3. In case of any clarification/ queries regarding online registration/ participation, Bidders may reach out to: Email: psbsupport@c1india.com
Ph.: 0124-4302033/36/37.
4. It is suggested that the prospective Bidders shall monitor the <https://psb.eproc.in> website constantly for any changes / updates.

Note:

1. Bank expects the interested Bidders to download the copy of the complete RFP document along with all Annexure & Appendices either through Bank's website <http://punjabandsindbank.co.in> or <https://psb.eproc.in>
Earnest money deposit of **Rs. 110000.00/-** (EMD (Refundable) should be deposited in the
Account Number:- 17325040070003
Name of Account:- NEFT INWARD STP PARKING ACCOUNT
IFSC-PSIB0021732
BRANCH: TARNA BAZAR VARANASI
OR Demand Draft (DD) in Favor of
"Punjab and Sind Bank, REGIONAL office Varanasi"

2. Bank expects the interested Bidders to download the copy of the complete RFP document along with all Annexure & Appendices either through Bank's website <http://punjabandsindbank.co.in> or <https://psb.eproc.in>

Notice Inviting: E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK OFFICE-RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712

Bank invites E-tenders in Two Bid Systems i.e. Technical Bid & Commercial Bid from Interior Contractors for the **E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH – RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712**

In case of any queries, the Tenderer may contact following:

Punjab & Sind Bank: Chief Manager Mob. No. 7837671366
Manager- Mobile no: 8299755730

ARCHITECT:

M/S Vaastu Vikalp Architects
S-24, First Floor S2S Square,
Garh Road, Meerut -250002
Mobile – 9899328602,9997591118

1. INTRODUCTION

Bank invites E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH OFFICE RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712
ELIGIBILITY CRITERIA

The invitation of bids is open to all service providers, provided they fulfil the following eligibility criteria.

CRITERIA	DOCUMENTS REQUIRED AND TO BE UPLOADED
a) The bidder should have at least 5 years satisfactory experience in providing similar works in Government Banks, Private sector. Banks, Government PSU and reputed Private Organizations Similar work means interior furnishing /Civil / fire alarm system / AC works of same nature / magnitude involving for offices etc. <u>Contractor's registered office should be in Uttar Pradesh and furniture workshop in Uttar Pradesh</u>	Work order and satisfactory completion certificate (on the letterhead of service recipient with complete address and telephone no.) in having executed similar category contract/s (in the city under consideration only) during the last 5 years (minimum) ending day before the invitation of this tender should be provided. The scope of works carried out, period of contract, Staff employed and value of work should be clearly defined.
b) The bidder should have the following experience for having executed similar contracts during last five years ending 31.03.2025:- 1. At least One (1) work of value of Rs. 17 Lacs 2. Two (2) works of value Rs. 13 Lacs or 3.Three (3) works of value Rs. 11 Lacs And Out of which one work of similar nature of minimum amount of 11 Lacs should have been executed in Uttar Pradesh	Work completion certificate should be provided on the letterhead of the Organisation where the work has been executed. With Stamp & Sign of the competent authority.
c) The bidder must have an average Annual Turnover of Rs. 25 Lacs by way of providing services during the last 5 years in similar contracts in Uttar Pradesh ending 31.03.2025.	1. Audited CA certified Profit & Loss statement for financial year 2020-2021, 2021-2022, 2022-2023 and 2023-2024,2024-2025. 2. self-attested Profit & Loss A/c and Balance Sheet (duly attested by the CA).
d) The bidder should not be declared by any Public Organization, to be ineligible to participate for corrupt, fraudulent or any other unethical business practice and Blacklisted by Public Organization.	A Self- declaration certificate that the bidder has not been declared by any Public Organization to be ineligible to participate for corrupt, fraudulent or any other unethical business practice and Blacklisted by Public

e) The bidder should be registered with the following statutory authorities: - Income Tax, GSTIN.	Photocopies of valid registrations/ license and latest challans should be furnished with the Tender.
f) Bidder should have sufficient resources namely manpower & equipment to execute the subject work.	Full list of sub-contractors/employees viz. Name, age, employee code, designation, experience in the field etc. and also the list of equipment proposed to be deployed as per Annexure D Should be attached. BAR/PERT Chart should also be submitted indicating the execution of the work within the date line of 30 days.
g) To ensure transparency, equity, and competitiveness in compliance with the CVC guidelines, this tender shall be covered under the Integrity Pact (IP) policy of the Bank. The pact essentially envisages an agreement between the prospective bidders/vendors and the Bank committing the persons/officials of both the parties, not to exercise any corrupt influence on any aspect of the contract.	The IP agreement enclosed at annexure must be Sealed and signed. <i>Any vendor/bidder not signed the document or refusing to sign shall be disqualified in the bidding process.</i>

*Amount mentioned above is excluding GST.

3. SCOPE OF WORK

The Contractor shall carry out and complete the said civil work, ac work, fire alarm system work, furnishing works comprising of wooden partition, panelling false ceiling including miscellaneous, electrical works and modification/addition to existing provision. Provision and Furniture, furnishing etc. complete in every respect in accordance with Contract and with the directions of and to the satisfaction of the Architects and the Bank. The Architects may in their absolute discretion and from time to time, issue further drawings and/or written instructions, details, directions and explanations which are hereafter collectively referred to as "Architect's Instructions" in regard to:

- a) The variations or modifications of the design quality or quantity of works or the addition or omission or substitution of any work.
- b) Any discrepancy in the drawings or between the Schedule of Quantities and/or drawings and/or Specifications.
- c) The removal and / or re-execution or any works executed by the Contractor.
- d) The removal from the site of any material brought there on by the contractor and the substitution of any other material there from.
- e) The dismissal from the works of any person / persons employed thereupon.
- f) The opening up for inspection of any work covered up.
- g) The amending and making good of any defects under clause "Removal of Improper Work and Material".

The Contractor shall forthwith comply and fully execute any work comprised in such Architect's Instructions provided always that verbal instruction. Directions and explanations given to the Contractor or his representative upon the works by the Architects shall, if involving a variation, be confirmed in writing by the Contractor within 3 days and if not dissented from in writing within further 3 days by the Architect. Such shall be deemed the Architect's instructions within the scope of the contract. If compliance with the Architect's instructions as previously mentioned involved work and/or expense and/or loss beyond that contemplated by the Contract. Then unless the same were issued owing to some breach of this contract by the Contractors. The Bank shall pay to the Contractor on the Architect's Certificate, the price of the said work (as an extra to be valued as herein after provided) and/or expense and/or loss

4. TENDER AND BID SUBMISSION

- a) Bids are invited from **Civil Interiors, furnishers/contractors located in Uttar Pradesh** who are eligible to do business in India under relevant Indian Laws as in force at the time of bidding. **Contractor's registered office should be in Uttar Pradesh.**
- b) Bidders who wish to participate will have to register with the website (<https://psb.eproc.in>). Bidders will be required to create login id & password on their own in registration process
- c) The bidder will be given permission to inspect the site, with prior appointment and up to one day prior to the last date of submission of the tender.
- d) The Bank shall not consider any request for date-extension for bid-submission on account of late receiving / downloading of Tender by any prospective service provider.
- e) The Bank also reserves the right to amend the tender prior to the last date for bid- submission. The Bank may at its discretion, extend the last date for bid-submission on any justified ground.
- f) The Bidder shall bear all the costs associated with the preparation and submission of bid and Punjab & Sind Bank will in no case be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process.
- g) Earnest money, Technical Bids and Commercial Bids are to be duly signed and super scribed a:
"E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH OFFICE- RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP- 221712.

5. AUTHORITY TO SUBMIT BIDS

- a) Only authorized personnel of the firm or organization shall sign the Bid.
- b) The proposal must be accompanied with an undertaking letter duly signed by the designated personnel providing a Bid commitment. The letter should also indicate the complete name and designation of the personnel.
- c) In case the principal service providers authorize their business partners to bid on their behalf, a separate authorization letter as per format (Letter of Authorization to bid) enclosed, along with a commitment to fulfil the terms of tender should be submitted.
- d) The certified photocopy of Resolutions/Authority/ Power of Attorney having authority to authorize the person to submit Bid documents on behalf of the company shall be enclosed.

6. BID CONTENTS

6.1 TECHNICAL OFFER TO BE UPLOADED:

- a) The Technical Offer (T.O.) should be completed in all respects and contain full information required in the documents.
- b) It should not contain any price information. It is mandatory to submit the technical details in the Prescribed format duly filled in along with the offer.
- c) In case of non-submission or partial submission of technical details, the Bank at its discretion may not evaluate the offer.
- d) The T.O. must be submitted in an organized and structured manner.

6.2 COMMERCIAL OFFER TO BE UPLOADED

- a) The Price quoted should be only in Indian Rupees.
- b) The rates quoted in the Bid shall be inclusive of all labour charges, delivery & cost of material at site tools & equipment, insurance premium covering any risk to labour etc. and taxes and all other taxes applicable.
- c) The Bids with correction and or overwriting, if not authenticated, will be **liable for rejection.**
- d) No claim for rate enhancement/price revision should be considered during the pendency of the contract.

6.3 EARNEST MONEY (Tender Fee and EMD):

Earnest money deposit of **Rs. 110000.00/-** (EMD (Refundable) should be deposited in the

Account Number:-17325040070003

Name of Account:- NEFT INWARD STP PARKING ACCOUNT

IFSC-PSIB0021732

BRANCH: TARNA BAZAR VARANASI

OR Demand Draft (DD) in Favor of

“Punjab and Sind Bank, Varanasi”

- b) No interest would be payable on the earnest money deposit amount.
- c) This amount would be forfeited if the bidder withdraws his bids during the period of bid validity.
- d) The earnest money must be submitted along with technical offers.
- e) In the event of non-submission of earnest money deposit, the proposal would be rejected.
- f) EMD would be released to the unsuccessful bidders after signing of the contract agreement by the L1 bidder.
- g) EMD of the successful bidder shall be released after submission of the **Performance Bank Guarantee/Fixed deposit of 5%** of Bid Value to be deposited to Bank.
- h) If the Bid price offered by the selected bidder is lower than 25% of the estimated project cost/cost put to tender, the additional performance security shall be calculated @ 50% of the difference in the Estimated Project Cost (as mentioned in RFP) and tendered cost.
- i) MSE/ MSME bidders are exempted from payment of Earnest Money Deposit (EMD)

7. BID FEATURES

- a) All bids and supporting documentation shall be submitted in English only.
- b) All costs and charges related to the bid shall be expressed in Indian Rupees (in INR) only.
- c) The bids shall be valid for a period of 03 months from the date of submission of bids. The Bank as non-responsive shall reject a bid valid for a shorter period.
- d) The file uploaded on the portal should have the name of document submitted in it.

8. BID ESSENTIALS - CONTENTS OF DOCUMENT TO BE SUBMITTED ELECTRONICALLY

The bidder shall submit the following:

- a) The Bank in case of non-adherence to the Format or partial submission of bid will not evaluate the bid.
- b) Each page of it shall be serially numbered, signed and duly stamped by the bidder or a duly authorized person to sign on behalf of the Service provider,
- c) Any interlineations, erasure or overwriting shall be valid only if these are initialled by the person(s) signing the bid.

APPENDIX TO GENERAL CONDITIONS OF CONTRACT

A	Mobilization Period	7 days from the date of Work Order
B	Date of Commencement of work on site	7 days after the date of Work order
C	Completion Period	30 days from date of commencement
D	Earnest Money Deposit	@110000.00
E	Security deposit	@ 5% of contract value refundable on virtual completion
F	Retention Money	5% of the payment
G	Defects Liability Period	12 Months from date of Virtual Completion
H	Liquidated Damages for Delay	1% per week up to max. of 10% of Contract value
I	Period of Final Measurement	1 month
J	Period of honouring Interim Certificate	7 working days from receipt of certification of Architect

Signature of Contractors:

Date:

Witness:

INSTRUCTIONS TO BIDDERS

1. Invitation of Bids:

This Request for Proposal (RFP) is to invite proposals from eligible bidders desirous of taking up the project for E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, FIRE ALARM SYSTEM, AIR CONDITIONING AND ELECTRICAL WORKS OF PUNJAB & SIND BANK BRANCH OFFICE- RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712

Sealed offers /Bids (Bid) prepared in accordance with this RFP should be submitted as per details given in the Key Information sheet. The criteria and the actual process of evaluation of the responses to this RFP and subsequent selection of the successful bidder will be entirely at Bank's discretion.

2. Due Diligence:

The Bidder is expected to examine all instructions, forms, terms and specifications in this RFP and study the RFP document carefully. Bid shall be deemed to have been submitted after careful study and examination of this RFP with full understanding of its implications. The Bid should be precise, complete and in the prescribed format as per the requirement of this RFP. Failure to furnish all information required by this RFP or submission of a Bid not responsive to this RFP in each and every respect will be at the Bidder's own risk and may result in rejection of the Bid and for which Punjab and Sind Bank shall not be held responsible.

Photocopies of relevant documents/ certificates duly stamped and signed by authorized person, must be submitted as proof in support of the claims made. The Bank reserves the right to verify/ evaluate the claims made by the Bidder independently. The decision of the Bank in this regard shall be final, conclusive, and binding upon the Bidder.

TECHNICAL BID TO BE UPLOADED:

- a) Service Provider's Profile (Annexure A) to be uploaded:
- b) All pages of bid document must be signed and stamped.
- c) Earnest Money Deposit (EMD) of Rs. **110000.00/-**
- d) Copy of satisfactory performance certificate of min. amount of below mentioned work on letter head of organization where the work has been executed duly signed and stamped by the competent authority –
 - i. At least One (1) work of value of Rs. 17 Lacs or
 - ii. Two (2) works of value Rs. 13 Lacs or
 - iii. Three (3) works of value Rs. 11 Lacs

Out of which one work of similar nature of minimum amount of 11 Lacs should have been executed in Uttar Pradesh.

*Amount mentioned above is excluding GST.

1. Audited/self-attested Profit and Loss Account and Balance sheet for the financial year ending on 2020-2021, 2021-2022, 2022-2023 and 2023-2024,2024-2025.
- e) Letter of Authorization to Bid.
- f) Power of Attorney (if any).
- g) List of contracts executed during last 5 years. (Annexure B).
- h) Past Performance (Annexure C).
- i) Organizational Setup - Details of Key skilled, semi-skilled and unskilled workers employed (Annexure D)
- j) Details of Litigation/Arbitration (Annexure E)
- k) Latest I.T.R. of FY 2023-24 or 2024-25
- l) Copy of Certificate of Incorporation (If Applicable)
- m) Copy of Memorandum of Association
- n) Copy of GST Certificate
- o) Copy of PAN Card
- p) Copy of PF Registration
- q) Copy of ESI Registration
- r) **A Self- declaration certificate that the bidder has not been declared by any Public/Private Organization to be ineligible to participate for corrupt, fraudulent or any other unethical business practice and Blacklisted by Public/Private Organization.**
- s) Other information -Any other relevant information, which is necessary to be furnished, must be provided.

3. BID EVALUATION

- a) The tenders received within the due date and time only will be considered for evaluation.
- b) The Technical bids shall be opened and the bid/s received will be scrutinized to determine whether they are complete in all respects as per the requirement of tender and subsequent clarifications, whether the documents have been properly signed and whether items are offered as per these tender requirements.
- c) The Bank will examine the bids to determine whether they are complete, whether any computational errors have been made, whether required information have been provided as underlined in the bid document, whether the documents have been properly signed, and whether bids are generally in order.
- d) Technical bids of the service providers meeting the minimum pre-qualification criteria will be evaluated for compliance of other terms and conditions.
- e) Based on the evaluation results, the bank will shortlist the bidders who are considered to be suitable. The decision of the Bank regarding the short-listing of the bidders shall be final and binding on the bidder.
- f) The commercial bids of only the successfully qualified bidders whose Technical bids are found acceptable will be opened subsequently on the date that will be conveyed to them.
- g) Arithmetical errors will be rectified on the following basis. If there is a discrepancy between unit price and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail and total price shall be corrected. If the supplier does not accept the correction of the errors, its bid will be rejected.
- h) If there is discrepancy between words and figures, the amount in the words will prevail.

- i) The L1 bidder will be determined based on the evaluation method as detailed in the next clause.
- f) **No discount should be given while submitting the price bid. Discount offered if any shall be liable for rejection of that bid.**

Any incomplete or ambiguous terms/conditions/quotes will disqualify the offer.

4. CLARIFICATIONS OF BIDS

To assist in the examination, evaluation and comparison of bids the Bank may at its discretion ask the bidder for clarification and response shall be in writing and no change in the price or substances of the bid shall be sought, offered or permitted.

5. NOTIFICATION OF AWARD

The acceptance of a tender, subject to contract, commercial considerations & compliance with all the terms and conditions will be communicated in writing by means of placing order at the address supplied by the bidder in the tender response. Any change of address of the Service provider, should therefore be promptly notified to *The REGIONAL Manager , Punjab & Sind Bank, REGIONAL Office, , Varanasi – 221 003* and written confirmation of such notification obtained.

6. SIGNING OF CONTRACT

The successful bidder shall be required to enter into a contract with PSB within 7 days of the award of the tender/ Letter of Intent or within such extended period as may be specified by The REGIONAL Manager , Punjab & Sind Bank, REGIONAL Office Shivpur Varanasi, – 221 003

TERMS AND CONDITIONS OF TENDER

DIRECTIONS REGARDING PROCEDURES

In construing these conditions, specifications and Contract Agreement, the following words shall Have the meaning here in assigned to them except where the subject or context otherwise requires:

- (a) **"Bank"** Shall mean *Punjab & Sind Bank, REGIONAL Office, Varanasi – 221 003* and shall include his (their) legal representative/s assign/s or authorized officer.
- (b) **"Contractor/Builder"** Shall mean the individual or firm or company, whether incorporated or not, undertaking the work and shall include legal personal representatives of such individual or the persons comprising such firm or company or the successors of such individual or firm or company and the permitted assignee of such individual or such individual or firm or company.
- (c) **"Architect"** Shall mean **"M/S Vaastu Vikalp Architects whose registered office is situated at S-24, First Floor S2S Square, Garh Road, Meerut - 250002"**(and shall include his authorized representative) or in the event of his death or termination of his services by the Bank in his sole and unqualified discretion, such other person/persons as shall be provided always that no person subsequently appointed to be Architect under this contract shall be entitled to disregard or over rule any previous decision or direction given or expressed by the Architect specified here in unless otherwise approved by the Bank.
- (d) **"Contract"** Means the documents forming the tender and acceptance thereof and the formal agreement executed between the competent authority on behalf of The REGIONAL Manager , Punjab & Sind Bank, REGIONAL Office Varanasi, – 221 003 and the Contractor, together with the documents referred to there in including these conditions, the specifications, designs, drawings and instructions issued from time to time by the Engineer-in-Charge and all these documents taken together, shall be deemed to form one contract and shall be complementary to one another.
- (i) The expression **works** or **work** shall, unless there be something either in the subject or context repugnant to such construction, be construed and taken to mean the works by or by virtue of the contract contracted to be executed whether temporary or permanent, and whether original, altered, substituted or additional.

1. GENERAL

- i. The **site** shall mean the land/or other places on, into or through which work is to be executed under the contract or any adjacent land, path or street through which work is to be executed under the contract or any adjacent land, path or street which may be allotted or used for the purpose of carrying out the contract.
- ii. **Schedule(s)** referred to in these conditions shall mean the relevant schedule(s).
- iii. **Tendered Value** means the value of the entire work as stipulated in the letter of award of work.
The work shall be carried out strictly in accordance with the drawings amplified by the specifications of materials and workmanship given hereunder. The drawings and specifications shall be taken together and shall complement each other. In case of any discrepancy, the following order of preference shall be followed:
 - (a) Particular Specifications.
 - (b) Drawings.
 - (c) CPWD Specifications & DSR 2021.
 - (d) National Building Code and Relevant IS Provisions.

In case there are no specifications for items shown on the drawings or where items are not exhaustively described, the general specifications of CPWD shall be followed for which nothing extra shall be paid. However, the specification should be got approved from the Architect before commencement of work.

2. DRAWINGS AND SPECIFICATIONS

- (a) After signing the Contract, the contractor will be given free of charge three prints of all working drawings. The contractor shall make at his own expense any additional copies he requires. One copy of the drawing furnished to the contractor as aforesaid shall be kept by the contractor at site and the same shall at all reasonable times be available for inspection and use by the Architect and his representatives any by any other person authorized by him in writing.
- (b) Such further drawings and instructions including revisions, as the Architect may furnish to the Contractor shall form part of this contract.
- (c) Only figured dimensions and detailed drawings shall be followed. The Contractor shall verify all dimensions in the field before any work is started and obtain instructions of the Architect in case of any discrepancy.
- (d) The Architect with approval of the *The REGIONAL Manager , Punjab & Sind Bank, REGIONAL Office Varanasi, – 221003* shall have power and authority to supply to the Contractor from time to time during the progress of the work, such further drawings and instructions as shall be necessary for the purpose of proper and adequate execution and maintenance of work and the Contractor shall carry out and be bound by the same.

3. SCHEDULE OF QUANTITIES:

The Schedule of Quantities unless otherwise stated shall be deemed to have been prepared in accordance with the method of measurements specified in the particular specifications and shall be considered to be approximate. The Bank does not undertake to carry out the whole of work as shown in the drawings and taken in the schedule of quantities and reserves the right to modify the same or any part thereof. The Contractor shall not be allowed any compensations or damages for the work so omitted or cancelled by the Bank. Each tender item should be filled in with the rates and amounts in separate columns and all the sections should be totalled up in order to show the aggregate value of the entire tender. The rates should be filled both in figures and words for each item and in case of discrepancy the rates filled in words shall be considered as correct for the evaluation of tender amount. The initials of the tenderers shall duly attest all corrections in the tender Schedule. Corrections, which are not attested, may entail the rejection of tender.

4. ARCHITECTS STATUS AND DECISIONS

(a) Status:

The Architects shall have general supervision and direction of the work. He has authority on behalf of the Bank to stop the work whenever such stoppage may be necessary to ensure the proper execution of the work. The architect shall be the interpreter of the conditions of contract and the judge of its performance.

(b) Decisions:

The Architect shall, within a reasonable time, make decisions on all claims of the contractor and on all other matter relating to the execution & progress of the work or the interpretation of the contract documents. The decisions, opinion or direction of the Architects with respect to all or any of the following matters shall be referred to the Asstt. General Manager (Premises), PSB and decision so taken shall be final & binding to the contractor.

Variation or modifications of the design.

- i. The quality or quantity of works or the additions/alterations or omissions or substitutions of any work.
- ii. Any discrepancy in the drawings or between the drawings and or specifications.
- iii. The removal and / or re-execution of any work by the contractor.
- iv. The dismissal from the work of any persons employed therein.
- v. The opening up for inspection of any work covered up.
- vi. The amending the making good of any defects under defects liability period.
- vii. Approval of materials and workmanship.
- viii. The contractor to provide everything necessary for the proper execution of the work.

(c) Dismissal:

The contractor shall on the report of the architects immediately dismiss from the works within 24 hours any person employed by him for the above work, who may, in the opinion of Architects be incompetent or misconducts himself and such person shall not be re-employed on the works without the permission of the Architects.

5. EXTENT OF CONTRACT

The contractor shall supply at his own cost all material implements, ladders, cordage, tackle, scaffolding and temporary works required for the proper execution of the work whether original, altered or substituted and whether included in the specifications or other documents forming part of the contract or referred to in these conditions or not and which may be necessary for the purpose of satisfying of conditions he is entitled to be satisfied which he is entitled to require together with carriage therefore to and from the work. The contractor shall also supply survey instruments and other materials necessary for the purpose of setting out works, and counting weighing and assisting to the measurement or examinations at the any time and from time to time of the work material, failing his so doing the same may be provided by the engineer-in-charge at the expense of the contractor and the expenses may be deducted from any money due to the contractor under the contract from his security deposit or the proceeds of sale thereof. The contractor shall also provide a sufficient portion of fencing and lights required to protect the public from accident, and shall be bound to bear the expenses of defence brought by any person for injury sustained owing to neglect of the above precautions and to pay any damage and costs which may be awarded in any such suit, action or proceedings to any such person or which may with the consent of the contractor be paid to compromise any claim by any such person. In no case, the Bank shall be a party to any such claim/claims and the contractor shall indemnify the Bank against any claim for any person on this account.

6. ASSIGNMENT OR SUB LETTING OF CONTRACT

The contractor shall not assign the contract or any part thereof or any benefit or interest therein or there under or any claim arising out of the contract to any other party without the prior written consent of the Bank.

7. CONTRACTORS OFFICE AND STORES

All offices, sheds and stores required by the contractor shall be enacted at his own cost with the prior approval of the Bank or its representative and shall be dismantled and removed upon the completion of the work if so directed within 7 (seven) days of the issue of such intimation.

8. DIRECTION FOR EXECUTION OF WORK

8.1 Setting outs

The contractor shall be responsible for the true and proper setting out of the works in relation to the original points, lines and levels of reference given by the architect in writing and for correctness subject as above mentioned of all the positions, levels dimensions and alignments of all parts of the work and for the provision of all necessary instruments, appliances and labour in connection there- with. If at any time during the progress of the work any error shall appear or arises in any part of the work, the contractor on being required to do so by The REGIONAL Manager , Punjab & Sind Bank, REGIONAL Office Varanasi shall at once inform the architect or their representatives. The checking of the work by the architect/representative shall not in any way relieve the contractor from his responsibilities of carrying out the work as per the best practices of construction.

8.2 Engagement of Labour

- (a) The contractor shall be solely responsible for the labour/ personnel employed and that the personnel provided by the contractor shall and will not make any claim to become employees of the Bank and that there will be no Employee and Bank relationship between the personnel engaged by the Contractor and the Bank.
- (b) The contractor shall employ labour in sufficient numbers either directly or through subcontractors, where such subletting is permitted to maintain the required rate of specified in the contract and to the satisfaction of the architect. The contractor shall not employ in connection with the works any person who has not completed his fifteen years of age.
- (c) The contractor shall comply with the provisions of the payment of Wages Act, 1936; Minimum Wages Act, 1948; Act, 1947; Maternity Benefit Act, 1961 and Mines Act, 1938, Labour Contract (Regulations & Abolishing) Act or Rules, or any modifications thereof and any other law relating thereto and rules made there under time to time.
- (d) The Contractor shall be fully responsible for timely monthly payment of wages and any other dues to the personnel deployed by the Contractor. Further the Contractor shall solely be responsible for having made the payments towards ESI and EPF amount (both Banks and employee's contribution) in the respective account of the worker for the period for which bill is raised.
- (e) The contractor shall indemnify the Bank against any payment to be made under and for observance of the Regulation aforesaid without prejudice to his right to claim indemnity from his sub-contractors.
- (f) The contractor shall provide and maintain at his own expenses all rights, guards, fencing and watching when and where necessary or required by the Resident Engineer for the protection of the works or for the safety and convenience of those employed on works or the public.

8.3 Sampling

- (a) The contractor shall submit the samples of various materials for the approval of the Architect & Bank. The contractor shall use the material only after the approval of the Architect/ Bank. The verification of the material shall be done on random base during the progress of the work in either the following manner:
- (b) Random samples would be picked up during execution of work from site & if decided by the Architect/ Bank, it would be sent to one of the approved laboratories for test & quality check. The cost of such tests would be borne by the client.
- (c) The Architect/ Bank may direct the contractor to submit the challan of delivery of the material brought at site. It would be on Random based. The Architect may also direct the contractor to submit the copy of the test/verification certificate provided by the manufacturer of that particular material.

8.4 Inspection of work

All work under or in course of execution or executed in pursuance of the contract shall at all times be open to inspection and supervision of the Architect or his representative and to the personnel and the representatives of the Bank and the contractor shall at all times with reasonable notice or the intention of the Architect or his representatives to visit work shall have been given to the contractor, either himself be present to receive orders and instructions, or have responsible agent duly accredited in writing present for that purpose. Orders to the contractor's agent shall be deemed to have been given to the contractor himself.

8.5 Suspension of Work

The contractor shall on the written order of the Architect/Bank suspend the progress of the work or any part thereof for such time or time and in such a manner as the Architect/ Bank may consider necessary and shall during such suspension properly protect and secure the work as considered necessary in the opinion of the Architect/ Bank or their representative-in-charge of the work. No compensation shall be payable to the contractor on what so ever account for the suspension of work.

8.6 Extension of time for completion

Time is the essence of the contract. The owner and the contractor in consultation with the Architects shall agree upon the work progress chart. The chart shall be prepared in direct relation to the time stated in the contract or the works order for completion of the individual items thereof and/or the contract or works order as a whole. It shall indicate the forecast of the dates of commencement and completion of the various trade processes or sections of the work and shall be amended as may be required by agreement between the architects and the Contractor within the limitations of time imposed in the contract. If the works be delayed:

- (a) By force majeure, or
- (b) By reasons of abnormally and bad weather
- (c) By reason of serious loss or damage by fire or
- (d) By reason of civil accommodation local combination of workmen or strike or lockout effecting any of the trades employed on the work or
- (e) By reason of delay on the part of contractor or trade men engaged by the owner in executing works not forming part of the contract or
- (f) By reason of proceeding taken threatened by or dispute with adjoining or neighbouring owners or public authorities arising otherwise, then through the Contractor's own default, or
- (g) By reason of any other cause which in the absolute discretion of Owner is beyond contractor's control then in any such case the owner may make fair and reasonable extension after obtaining Architect's advice in the completion dates of individual items or groups of items of work for which separate periods of completion are mentioned in the contractor or works order as applicable.
- (h) Upon the happening of any such event causing delay, the contractor shall immediately give the notice thereof in writing to the architects with a copy to Bank but shall nevertheless use constantly his best Endeavour to prevent or make good the delay and shall do all that may reasonably be required to the satisfaction of the Architect/Bank to proceed with the works Extension of time shall be granted.

8.7 Defacement

If the contractor or his work people, or servants shall break, deface, injure, or destroy any part of a Building, or interiors, then the contractor has to rectify the same part at his own expenses to the satisfaction of the Architect/ Bank's in charge engineer.

8.8 Approval of Materials

The contractor would bring samples of necessary materials as per the directions & would get them approved prior to execution of work from Architect.

9. LIQUIDATED DAMAGES FOR DELAY

The times and date stipulated in the contract for the completion of the work or any part or stage There of shall be deemed to be the essence of the contract. The work shall, throughout the stipulated period of the contract, be carried out with all diligence. If the contractor fails to complete the work within the time prescribed or within the extended time under the contract, he shall pay to the Bank on demand amount without prejudice to other rights and remedies the Bank may have against the contractor, **1% of contract price per week** or part there of as liquidated damages for such fault, if the work remain unfinished after the stipulated date of completion provided that the total liquidated damages payable shall not exceed 10% of the accepted contract price. The Bank may, without prejudice to any other method of recovery, deduct the amount of such damages from any money due or which become due to the contractor. The recovery or deduction of such damages shall not relieve the contractor from any obligations and liabilities under the contract.

10. DEFECTS LIABILITY PERIOD

The contractor shall be responsible to make good and remedy at his own expense within such period as may be stipulated by the Bank any defect which may develop or may be noticed before the expiry of 12 (twelve) calendar months from the date of completion and intimation of which has been sent to the contractor within seven days of the expiry of the said period. Total of 5% of the contract value shall be retained by the bank up to the completion of defect liability period. In case the contractor fails to respond to the bank notification in sufficient time for repair (if/any) the above retention, money shall be utilized by the bank for such repairs under intimation to the contractor.

11. SECURITY DEPOSIT

- (a) The Bank will, at the time of making any payment to the contractor for work done or supply Made under the contract deduct 5% of Gross value of each bill up to 5% of contract value.
- (b) All compensations or other sums of money payable by the contractor to the Bank in terms of this contract may be deducted from, or paid by, the sale of a sufficient part of his security deposit, or from any sums which may become due to the contractor by the Bank on any ac- count whatsoever, and in the event of his security deposit being reduced by reason of any such deduction or sale as aforesaid, the contractor shall within ten days. Thereafter make good in demand draft, endorsed in favour of the Bank as aforesaid any sum or sums which may have been deducted from, or raised by sale of his security deposit or any part thereof.
- (c) The above said security deposit shall be liable to forfeiture wholly or in part at the sole discretion of the Architect if the contractor fails to carry out the work or perform or observe any of the conditions of the contract.
- (d) No interest would be payable by the Bank to the contractor on the security held in deposit.

12. BILL PAYMENT

- (a) Final bill supported with consolidated measurement of the full work executed shall be submitted by the contractor within 30 days from the date of issue of certificate of virtual completion.
- (b) Architect/Bank or his representative shall verify the requisite measurement for the purpose of having the same verified for the claim as far as admissible.

(c) All measurements to be taken in duplicate and all bills shall be submitted in triplicate along with a contractor's copy of each.

(d) When the final bill has been verified and corrected, the architect will give seven days' notice to The contractor to countersign the bill in token of acceptance, the contractor shall counter- sign the bill Within the above seven days or intimate in writing his intention to dispute.

(e) If the contractor fails to take appropriate action as above within the period prescribed, the bill Finalized by the architect or his representative shall be final and binding on the contractor and the Contractor shall have no right to dispute the same.

13. CLAIM FOR INTEREST

No claim for interest will be entertained by the Bank with respect to any moneys or balances which may be in its hands owing to a dispute between itself and the contractor or with respect of any delay on the part of the Bank in making interim or final payments or otherwise.

14. RATES FOR EXTRA ADDITIONAL, ALTERED OR SUBSTITUTED WORK

The rates for additional, altered or substituted work shall be worked out in accordance with the following provisions in their respective order

- (a) If the rates for similar additional, altered or substituted work and directly available in the contract for the work, the contractor is bound to carry out the work at the same rates as are available in the contract for the work.
- (b) If the rates for additional, altered or substituted work are not directly available in the contract for the work the rates will be derived from the rates for a similar class of work as are specified in the contract for the work.
- (c) If the rates for the altered, additional or substituted work cannot be determined in the manner specified in sub-clause (i) to (ii) above, then the contractor shall within three days of the date of receipt of order to carry out the work, inform the Architect of the rate which it is intending to charge for such works supported by analysis of the rate or rates claimed (CPWD analysis). Rates finalized and approved by the Architect on the basis of these details will be final and binding. However, the architect by notice in writing will be at liberty to cancel his order to execute such work and arrange to carry it out in such a manner as he may deem advisable, but under no circumstances shall the contractor suspend the work once ordered in writing on the plea of non-settlement of rate.
- (d) In case of furniture items, the minor changes and modifications in the design shall not be considered as deviation, and no price adjustment shall be made against the rates agreed to as per the Schedule of Quantities of the contract. For major change in the design of any item of the furniture, the deviation shall be priced by the Architects as Extra, as per above however the decision of the Architects whether the charge / modification in the design of furniture items is minor or major, shall be final and binding on the contractor.

14.1 REIMBURSEMENT OF VARIATION IN PRICE

Prices and rates quoted by the Tenderers shall be considered as confirmed for the complete work and entire duration of the contract. No claim for extra payment due to any rise in rates of raw material and labour or due to whatsoever reasons shall be considered, not even for extended period of completion.

15. GUARANTEES

15.1 Quality of Work

- (a) The contractor shall guarantee that the materials and workmanship are the best of their respective kinds for the service intended and that all items of work will be free from all inherent defects in workmanship and materials. He shall also guarantee that the works will not fail in any respect due to quality of materials, workmanship and methods of construction.
- (b) The specifications assume a proper degree of skill on the part of contractor and workmen employed. The contractor shall consult the Architect or his representative, whenever in his judgment variation in the methods of construction or in the quality of material would be beneficial or necessary to fulfil the guarantee is called for. Such variations may be made by the contractor only when authorized by the architect.

15.2 Rejection

If during the "Period of Guarantee", any work or material shall fail in any respect to meet the above guarantee, the contractor shall replace such work or material in a condition which will meet the above guarantee, immediately.

15.3 Cost of Execution of work or repair etc.

All work of repair shall be carried out by the contractor at his own expense if the necessity thereof shall in the opinion of the Architect be due to the use of materials or workmanship not in accordance with the contract or on account of neglect or failure on the part of the contractor to comply with any obligation expressed or implied on the contractor's part under the contract.

15.4 Remedy on Contractor's failure to carry out the work required:

If the contractor shall fail to do any such work as aforesaid required by the architect the Bank shall be entitled to carry out such work from/through other person, at the contractor's own cost. The Bank shall be entitled to recover from the contractor the cost thereof or may deduct the same from any money due or that may be come due to the contractor.

16. CERTIFICATE OF COMPLETION OF WORKS

On completion of the work, the Contractor shall be furnished with a certificate, but no such certificate be given nor shall the work be considered to have been completed until the contractor shall have removed from the area of the premises (to be distinctly marked by the Architect) in the site plan which, the work shall be executed) all scaffolding, surplus materials and rubbish and clean the dirt from all wood work, doors, windows, walls, floors or other parts of any building, in or upon which the work is to be executed, or of which he may have had in possession for the purpose of the execution hereof. If the contractor shall fail to comply with the requirements of the clause as to the removal of scaffolding, surplus materials and rubbish and cleaning off dirt on or before the date fixed for the completion of the work, the architect may at the expense of the contractor remove such scaffolding, surplus materials, and the contractor shall forthwith pay the amount of all expense so incurred, and shall have no claim in respect of any such scaffolding or surplus materials aforesaid, except for any sum actually realized by the sale thereof.

17. TERMINATION OF THE CONTRACT

- (a) If at any time after the commencement of the work the Bank for any reason whatsoever does not require the whole or part thereof as specified in the tender to be carried out, the Bank shall have the right to terminate this Agreement and The PSB shall communicate the termination by giving a notice in writing to the contractor.
- (b) The contractor shall have no claim to any payment or compensation whatsoever on account of any profit or advantage, which would have derived from the execution of the work in full, but which he did not derive in consequences the full amount of the work not having been carried out.
- (c) The Contractor shall not have any claim or compensation by reason of any alterations having been made in the original specification, or the designs and instruction on which shall involve any containment of the work originally contemplated. However, in case of part cancellation, the Contractor shall be paid such amount as is commensurate to the actual work done by him till such termination notice is received.

18. JURISDICTION & GOVERNING LAW

The contractor and its operation shall be governed by the law of India for the time being in force, irrespective of the place of delivery of materials the place of execution of work or place of payment under this contract shall be deemed to have been entered into Varanasi.

19. BYE LAWS OF LOCAL AUTHORITIES

The contractor shall conform to the provisions of all applicable Government Acts which relate to works and to the regulations and bye laws of any local authorities. The Contractor shall give all such notices required by the said Act or Laws, etc., and pay all fees payable to such authorities and allow for these contingencies in his tendered rates including fees for encroachment, stacking charges, costs of restorations, etc., and all other fees payable to the local authorities. The Contractor shall keep the Bank indemnified against all penalties and liabilities for every breach of any such Act, Rules, Regulations or Byelaws.

Further, the Contractor shall specifically ensure compliance of various Labour Laws/Acts including but not limited to with the following and their re-enactments/amendments/modifications while dealing with the employment of labour such as:

- i. The Payment of Wages Act, 1936
- ii. The Minimum Wages Act, 1938
- iii. The Workmen Compensation Act, 1923
- iv. The Contract Labour (Regulations & Abolishing Act.
- v. The Bank's Liabilities Act, 1938
- vi. Industrial Dispute Act, 1938
- vii. Maternity Benefit Act, 1961
- viii. The Employees State Insurance Act, 1948

Safety code, labour welfare Act or rules or any modification thereof any other laws and regulations framed by the Competent Legislative Authorities from time to time.

20. LIAISONING & CO-ORDINATION WITH LOCAL MUNICIPAL AUTHORITIES

The contractor has to liaison and takes any clearance from local authorities Fire/ Police or any other authorities for approval to start renovation and during renovation of work including Defect Liability Period if needed. Only statutory fees will be reimbursed by PSB.

SPECIAL CONDITIONS OF THE CONTRACT

1. INSURANCE FOR WORKS

(a) The contractor at the time of signing the contract or before commencing the execution of work, without limiting his obligations and responsibilities shall insure the works at his own cost and keep them insured until the virtual completion of the contract against all acts of God including Fire, Theft, Riots, War, Floods etc. with a Nationalized Insurance company in the joint names of the Bank and the contractor (the name of the former being placed first in the policy) for the full amount of the contract. Such policy shall cover the property of the Bank and fees for assessing the claim and in connection with the services generally therein and shall not cover any property of the Contractor or of any sub-contractor or employee.

(b) The contractor shall deposit the policy and receipt for the premiums with the Bank within seven (7) days, from the date of signing of the contract/commencement of the execution of the work or unless otherwise instructed by the Bank. In default of the contractor insuring as provided above, the Bank on his behalf may so insure and may deduct the premiums paid from any moneys due on which may become due to the contractor. The contractor shall as soon any claim under the policy is settled on the work reinstated by the Insurance office should elect to do so, proceed with all due diligence with, the completion of the works in the same manner as through the misfortune/accident had not occurred and in all respects under the same conditions of the contract. The contractor in case of rebuilding or reimbursement after accident shall be entitled to such extension of time for completion, as the Bank deems fit.

2. INSURANCE IN RESPECT OF DAMAGE TO PERSONS AND PROPERTY

(a) The contractor shall be responsible for all injury to persons, animals or things and for all structural and decorative damage to property which may arise from the operation or neglect of himself or of any approved sub-contractor's or employees, whether such injury or damage arise from carelessness, accident or any other cause whatsoever in any way connected with the carrying out of this contract. The clause shall be held to include any damage to buildings, whether immediately adjacent or otherwise, and any damage to roads, streets, foot paths, bridges and works forming the subject of this contract by frost or other inclemency of the weather. The contractor shall indemnify the Bank and hold him harmless damage to persons or property as aforesaid and also respect of any claims made in respect of injury or damage under any Acts of Government or otherwise and also in respect of any award of compensation of damages consequent upon such claims.

(b) The contractor shall reinstate all damages of every sort mentioned in this clause, so as to deliver up the whole of the contract works complete and perfect in every respect and so as to make good or otherwise satisfy all claims for damage to the property of third parties.

(c) The contractor shall indemnify the Bank against all claims which may be made against the Bank by any member of the public or other third party in respect of works in consequence thereof and shall at his own expense arrange to effect and maintain, until the virtual completion of the contract, with any Nationalized Insurance company in the joint name of the Bank and the contractor against such risks and deposit such policy or policies with the Bank from time to time during the currency of this contract. The contractor shall similarly indemnify the Bank against all claims which may

be made upon the Bank whether under the Workman's Compensation Act or any other statute in force during the currency of this contract or at common law in respect of any employee of the contractor or any sub-contractor and shall at his own expenses effect and maintain with an approved office a policy of Insurance in the joint names of the Bank and the contractor against such risks and deposit such policy or policies with the Bank and the contractor against such risks and deposit such policy or policies with the Bank from time to time during the currency of the contract. The contractor shall be responsible for anything which may be excluded from the insurance policies above referred to and also for all other damages to any property arising out of and incidental to the negligent or defective carrying out of this contract. He shall also indemnify the Bank in respect of any costs, charges or expenses arising out of any claim or proceedings and also in respect of any award of or compensation of damages arising there from.

- (d) The Bank shall be at liberty and is empowered to deduct the amount of any damages, compensation costs, charges and expenses arising or occurring from or in respect of any such claim or damage from any sum or sums due to or become due to the contractor including the security deposit.
- (e) If the contractor fails to comply with the terms of these conditions, the Bank may insure the works and may deduct the amount of the premiums paid from any moneys that may be or become payable to the contractor or may at the option, not release running payment to the contractor until the contractor shall have complied with the terms of this condition.
- (f) Such insurance whether effected by the Bank or the contractor will not limit or bar the liability and obligation of the contractor to deliver the works to the Bank completed in all respects according to the contract. In case of loss or damage due to any of the aforesaid clause, the moneys payable under any such insurance shall be received and retained by the Bank until the works are finally completed and such moneys shall then be credited to the contractor in final settlement of accounts.
- (g) The works shall be executed in close co-ordination with the progress of other work. This being absence of the contract, no claim for idles labour will be entertained.

3. TYPOGRAPHIC OR CLERICAL ERRORS:

The Architect's/Engineer-in-Charge's clarifications regarding partially omitted particulars or typographical or clerical errors shall be final and binding on the Contractor.

- 4. Acceptance of tender:** - On acceptance of tender, the Bank shall issue a Letter of Intent (LOI) and shall enter into an agreement with 7 days from the issue of LOI. On the contrary, Bank has a right to cancel the order and for fit the EMD.
- 5.** Time shall be regarded as the essence of the contract. The work should be taken up immediately and completed within (as per terms and conditions attached) 30 days from the date of issue of work order.
- 6.** Contractor will be permitted to work normally during the regular working hours i.e. 9 a.m. to 6.00 pm. If the Contractor is required to work at night in order to complete the work within the Time Schedule, the Contractor shall seek written permission from the Bank for the same. Further, the contractor is liable provide and maintain at his own cost sufficient lights to enable the work to proceed satisfactorily without danger. Approaches to the site also shall be sufficiently lighted by the Contractor. No extra payments will be made for night work. Prior intimation and approval should

also be taken from Architect/Consultant. However, no work shall be done on national holidays that may be notified by the Bank without the specific sanction in writing of the Bank.

7. Contractor to coordinate and assist the Architect in obtaining all Statutory approvals including MMC, CFO and any other State and Central rules in force. Any expenses incurred in obtaining such approvals are deemed included in the rates quoted by the Contractors.
8. **Measurements of all concealed items:** Measurements of all concealed items of work and extra item if any, shall be got recorded by the Bank's Architect / Engineer before they are checked up.
9. **Cleaning during the work:** The rates quoted shall include cleaning of ceiling roses, electric switches, boards, window panes etc. after the repairing leaving the site neat and tidy from time to time.
10. The contractor shall note that they should bring to the notice of the Architect/Engineer any breakage in glass window before starting work. However, if any glass window is found to be broken during the repairing work, the contractor at his own cost shall replace the same.
11. **Abandonment of work:** If in any case the work required to be abandoned, the contractor shall not be entitled for any claims and he will be paid as per the actual work done till that period.
12. **For water proofing works** on traces, bathroom, WC, Chhajja, work has to be executed through the agency specialized in waterproofing. Contractor will have to submit a guarantee of 10 years on stamp papers as per the format to be prescribed by the Bank.
13. **Records & measurements:** Measurements shall be taken jointly by Bank's Architect / Engineer and contractor and shall without extra charges provide assistance with appliance; labour and other things necessary for the work and measurements will be signed and dated by both the parties on completion of measurements.
14. **Supervision:** The contractor is required to have on site during all working hours a competent supervisor (acceptable to Bank) who will be responsible for the conduct of worker and who has authority to receive and act on such instructions issued by the Architect / Engineer of Bank.
15. Contractor shall follow all rules / regulations in force and should possess the license for employing labour and also follow all safety measures, labour bye law and shall be responsible for any lapse.
16. **Safety:** The contractor shall carry out the entire work in a workman like manner having full regard for the safety of the men working at site. All safe practices as per CPWD norms shall be strictly adhered to by the workmen of the contractor like wearing helmets, safety belts when working at heights, gloves when handling sharp objects and reinforcement, eye shields during welding, safety shoes, etc. The contractor shall protect sides of openings in floor slabs, edges of slabs, stairs, stairwells etc. with barricades, warning signs / lights and educate all his workmen regarding following safe working

Practices. He shall provide first aid boxes at site. In spite of following safe methods, in case of any unfortunate accident, the contractor shall indemnify the employer against any expenses or claims towards treatment or compensation.

- 17. A Daily Diary Register:** A daily diary register (with cement and steel stock statement) will be kept in the Engineer's Office or the site office. Details of work for the day proceeding and the diary will be written up every day and jointly signed by the Engineer and the Contractor or their representatives in token of its correctness thereof.
- 18. Site Visits:** - The Architect/Consultant /Bank shall visit the site from time to time at their discretion, or when expressly called upon to do so, to co-ordinate various activities and/or to answer such queries that may be posed at site on interior drawings.
- 19. Certificate of virtual completion:** As soon as the work is completed, the contractor shall inform in writing such completion to the Bank's Architect / Engineer who will inspect the work and if satisfied will issue the certificate that the work has been virtually completed and the defects liability period shall commence from the date of such certificate.
- 20.** When the work has been virtually completed and Bank's Architects / Engineer has certified in writing that the work has been completed on the basis of detailed measurements and has made a final scrutiny and that there is no dispute items, rates, add quantities, the contractor shall be entitled to the payment of the final bill in accordance with the final certificate which will be honoured within the period specified in the Appendix as period of honouring final certificate.
- 21.** During the pendency of the contract, Bank reserves the right to cancel a part or whole of the order without assigning any reason, on 3 days' notice without any cancellation charges.
- 22.** Site must be cleaned and free from debris before payment of bills.
- 23.** Any loss/damage sustained to the Bank due to any act or omission on the part of the contractor or his men will have to be made good to the Bank by the contractor.

24. Force Majeure

The contractor shall not be liable for forfeiture of its performance security, liquidated damages or termination for default, if and to the extent that delay in performance or other failure to perform its obligations under the contract is the result of an event of Force Majeure. For purposes of this Clause, "Force Majeure" means an event beyond the control of the contractor and not involving the contractor's fault or negligence and not foreseeable. Such events may include, but are not limited to, Acts of god or of public enemy, acts of Government of India in their sovereign capacity, acts of war, acts of Punjab & Sind Bank either in fires, floods, strikes, lock-outs and freight embargoes.

If a Force Majeure situation arises, the contractor shall promptly notify Punjab & Sind Bank in writing of such conditions and the cause thereof within **15 days**. Unless otherwise directed by Punjab & Sind Bank in writing, the contractor shall continue to perform its obligations under the Contract as far as it is reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.

In such a case, the time for performance shall be extended by a period not less than the duration of delay. If the duration of delay continues beyond a period of three months Punjab & Sind Bank and the contractor shall hold consultations with each other in an endeavour to find a solution to the problem notwithstanding the above the decision of Punjab & Sind Bank shall be final and binding on the service provider.

25. Resolution of dispute

Punjab & Sind Bank and the contractor shall make every effort to resolve amicably, by direct informal negotiation, any disagreement or dispute arising between them under or in connection with the contract. If after 45 days from the commencement of such informal negotiations, Punjab & Sind Bank and the contractor is unable to resolve amicably a contract dispute; either party may require that the dispute be referred for resolution by formal arbitration.

All disputes, differences, claims and questions whatsoever arising from this Agreement between the parties and/or their respective representatives touching these presents or any clause or thing contained therein or otherwise in any manner relating to or arising from these presents shall be referred to the sole and the arbitrator shall be mutually appointed by both the parties. Any party desirous of making a reference to the Arbitrator shall give fifteen days Registered Acknowledgement Due notice of his intention to do so to the other party at his usual place of business or residence or of the place of their last notified address and the notice shall be deemed to have been served when it would ordinarily have been served when it would ordinarily have been sent by post. The notice sent by the arbitrator to the parties by Registered Post at the addresses mentioned in the Agreement will be considered sufficient service on the parties whether such notice is received by them or not is refused, or is returned undelivered.

It is further agreed that:

- (a) The place of arbitration will be Varanasi.
- (b) The arbitration proceedings will be governed by the Arbitration and Conciliation Act, 1996.
- (c) The arbitration proceedings will be in the English language.
- (d) The award will be recorded in writing, along with the reasons therefor.
- (e) The Parties shall equally share the costs of the arbitrators' fees,

CONFIDENTIALITY:

This tender document is confidential and is not to be disclosed, reproduced, transmitted, or made available by the Recipient to any other person. The Bank may update or revise the tender document or any part of it. The Recipient accepts that any such revised or amended document will be subject to the same obligation of confidentiality.

•All Punjab & Sind Bank product and process details, documents, data, applications, software, systems, papers, statements and business/customer information which may be communicated to or come to the knowledge of the selected bidder or its employees during the course of discharging their obligations shall be treated as absolutely confidential and the selected bidder irrevocably agrees and undertakes and ensures that the selected bidder and its employees shall keep the same secret and confidential and not disclose the same, in whole or in part to any third party without the prior written permission of Punjab & Sind Bank nor shall use or allow to be used any information other than as may be necessary for the due performance by the selected bidder of its obligations hereunder.

•The selected bidder shall not make or retain any copies or record of any Confidential Information submitted by Punjab & Sind Bank other than as may be required for the performance of the selected bidder obligation under this Agreement. The selected bidder shall notify Punjab & Sind Bank promptly of any unauthorized or improper use or disclosure of the Confidential Information.

•The selected bidder shall return all the Confidential Information that is in its custody, upon termination / expiry of this Agreement. Also, so far as it is practicable, the selected bidder shall immediately expunge any Confidential Information relating to the projects from any computer, word processor or other device in possession or in the custody and control by selected bidder or its affiliates.

•The selected bidder shall extent practicable, immediately furnish a certificate signed by its director or other responsible representative confirming that to the best of his/her knowledge, information and belief, having made all proper enquiries and these requirements have been fully complied with.

•The selected bidder hereby unconditionally agrees and undertakes that it and its employees shall not disclose the terms and conditions of this Agreement or disclose the information submitted by Punjab & Sind Bank under this Agreement to any third party unless such disclosure is required by law or for the purpose of performing any of its obligations under this Agreement.

•It shall be the incumbent duty of the selected bidder to undertake not to disclose any business related information of Punjab & Sind Bank to any third person and the selected bidder shall keep all knowledge of the business activities and affairs of Punjab & Sind Bank strictly confidential and also to ensure that neither the selected bidder nor any of its officers, employees directly or indirectly assist any third person with the promotion of activities which may be prejudicial to the interest or in competition to the activities of Punjab & Sind Bank.

•However, the confidential information will not be limited to the information mentioned above but not include the following as confidential information:

- Without breach of these presents, has already become or becomes and/or hereinafter will become part of the public domain;
- Prior to the disclosure by Punjab & Sind Bank was known to or in the possession of the selected bidder at the time of disclosure;
- Was disclosed or parted with the prior consent of Punjab & Sind Bank;
- Was acquired by the selected bidder from any third party under the conditions such that it does not know or have reason to know that such third party acquired directly or indirectly from Punjab & Sind Bank.

•The selected bidder agrees to take all necessary action to protect the Confidential Information against misuse, loss, destruction, deletion and/or alteration. It shall neither misuse or permit misuse directly or indirectly, nor commercially exploit the Confidential Information for economic or other benefit. Notwithstanding above Punjab & Sind Bank shall take all the reasonable care to protect all the confidential information of consultant while performing of the services.

•The provisions of this Clause shall survive the termination of contractual agreement.

Non-Disclosure Agreement (NDA) - The selected bidder shall execute Non Disclosure agreement in the format provided by the Bank within one month from the date of acceptance of letter of empanelment or signing of work order/SLA the NDA shall be executed by the authorized signatory of the successful Applicant. The date of letter of empanelment shall be treated as date of empanelment and the time-line for empanelment shall be worked out with reference to this date.

TENDER FORM

The REGIONAL Manager ,
Punjab & Sind Bank,
REGIONAL Office Varanasi,
Shivpur ,
Varanasi – 221 003

Dear Sir,

Having visited the site and examined the conditions of contract, Specifications and Schedule of Quantities for the above named works, I/We offer to undertake and complete the whole of the subject work in conformity with the said conditions of Contract, Specifications and Schedule of Quantities for the sum stated in Schedule of Quantities of this Tender Document or such other sum as may be ascertained in accordance with the said conditions of contract.

I/We undertake to complete and deliver the whole of the work comprised in the contract within **30 days**. We have independently considered the amount of liquidated damages, Contractors All Risk (CAR) insurance policy and Fire Insurance. The Contractors All Risk (CAR) and Fire insurance policy shall be obtained for the tender value in the joint names of Punjab & Sind Bank and Contractor from an approved Insurance Company for a Suitable period and the policy will be deposited with of Punjab & Sind Bank. Should this tender be accepted, I/We hereby agree to abide by and fulfil the terms and conditions of the said contract annexed here to so far as they are applicable or in case of default will pay to bank the amount mentioned in the said conditions. I/We agree to abide by this Tender till the Period of completion from the date fixed for receiving the same or agreed extended period and it shall remain binding upon us and may be accepted at any time before the expiry of the period. Unless and until a formal Agreement is prepared and executed, this tender together with your written acceptance thereof shall constitute a binding contract between us. I/We understand that if our tender is accepted, I/We are to be jointly and severally responsible for the due performance of the Contract.

2. I/We deposited a sum of _____ . As
earnest money in the form of Demand draft bearing no. _____ dated
_____ of _____ drawn in favour of **Punjab & Sind
Bank, REGIONAL office Varanasi** which is not to bear any interest. Should I/We fail to
execute the contract (as per banks Performa in non – judicial stamp paper) when called
upon to do so, the EMD may be forfeited by of **Punjab & Sind Bank**. I/We understand that
you are not bound to accept the lowest or any Tender you receive.

3. Our Bankers are:-

4. The name of our firm partners are:

BIDDER: -

Signature: -

Name: -

WITNESS Seal &

Signature: Name: -

DEED OF INDEMNITY
(to be executed on stamp paper)

This Deed of Indemnity executed at VARANASI on the _____ day of _____ by _____ (hereinafter referred to as “**the Obligor**” which expression shall unless it be repugnant to the context, subject or meaning thereof, shall be deemed to mean and include successors and permitted assigns);

IN FAVOUR OF PUNJAB & SIND BANK, a body Corporate constituted under the Banking Companies (Acquisition and Transfer of Undertaking) Act of 1980 having its Corporate Office at Punjab & Sind Bank, Plate-B, Block-3, NBCC Tower, East Kidwai Nagar, New Delhi (hereinafter referred to as “Punjab & Sind Bank” which expression shall, unless it be repugnant to the subject or context or meaning thereof, be deemed to mean and include its successors and assigns)

WHEREAS Punjab & Sind Bank vide its Tender No [-----] dated [-----] (Tender) had invited Bids from the eligible Bidders for Interior & Furnishing work at BRANCH OFFICE- Rasra – AT CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712 **WHEREAS**

1) The Obligor has

- a) Offered to Punjab & Sind Bank the service(s) as stated under Scope of Work of Tender;
- b) represented and warranted that it has all permissions, consents, approvals and license from all authorities, both regulatory / statutory and non-regulatory, for executing the services as stated in the Contract dated...../Tender;
- c) Represented and warranted that the aforesaid services offered to Punjab & Sind Bank do not violate any provisions of the applicable laws, regulations or guidelines. In case there is any violation of any law, rules or regulation, which is capable of being remedied the same will be got remedied immediately during the implementation, maintenance and contract period to the satisfaction of Punjab & Sind Bank;
- d) Represented and warranted that they are authorized and legally eligible and otherwise entitled and competent to enter into such Contract with Punjab & Sind Bank;

- 2) Punjab & Sind Bank, relying and based on the aforesaid representations and warranties of the Obligor, has agreed to avail the services from the Obligor on the terms and conditions contained in its Contract dated _____ (**the Contract**) with the Obligor;
- 3) One of the conditions of the aforesaid Contract/Tender is that the Obligor is required to furnish an indemnity in favour of Punjab & Sind Bank indemnifying the latter against any loss, damages or claims arising out of any violations of the applicable laws, regulations, guidelines during the execution and rendering/delivery of service(s) to Punjab & Sind Bank and/or due to breach of terms and conditions of the Contract by the Obligor and/or on account of misconduct, omission or negligence or otherwise by the Obligor.
- 4) In pursuance thereof, the Obligor has agreed to furnish an indemnity in the form and manner and to the satisfaction of Punjab & Sind Bank as hereinafter appearing;

NOW THIS DEED WITNESSETH AS UNDER: -

The words and expressions not specifically defined shall have the same meanings as are respectively assigned to them in the Tender/the Contract.

In consideration of Punjab & Sind Bank having agreed to award the Contract to the Obligor, the Obligor hereby unconditionally, absolutely and irrevocably agree and undertake that: -

- 1) The Obligor shall, at all times hereinafter, save and cause no harm and indemnified to Punjab & Sind Bank, including its respective directors, officers, employees, agents and representatives and keep them indemnified from and against any claim, costs, charges, damages, demand, losses, liabilities or expenses of any nature and kind whatsoever and by whomsoever made in respect of the Contract and any loss or damage caused from and against all suits and other actions that may be instituted taken or preferred against Punjab & Sind Bank by whomsoever and all losses, damages, costs, charges and expenses that Punjab & Sind Bank may incur by reason of any claim made by any claimant for any reason whatsoever or by anybody claiming under them or otherwise for any losses, damages or claims arising out of all kinds of accidents, destruction, deliberate or otherwise, direct or indirect, from those arising out of violation of applicable laws and also from the environmental damages, if any, which may occur or result from the terms of the Contract.
- 2) The Obligor further agrees and undertakes that the Obligor shall, ensure that all the permissions, authorizations, consents and licenses are obtained and renewed from the local

- 3) and/or municipal and/or governmental authorities, as may be required under the applicable laws, rules, regulations, guidelines, orders framed or issued by any appropriate authorities.
- 3) If any additional approval, consent or permission is required by the Obligor to execute and perform the Contract during the currency of the Contract, it shall procure the same and/or comply with the conditions stipulated by the concerned authorities without any delay.
- 4) The obligations of the Obligor herein are irrevocable, absolute and unconditional, in each case irrespective of the value, genuineness, validity, regularity or enforceability of the aforesaid Contract or other agreement, or the insolvency, bankruptcy, reorganization, dissolution, liquidation or change in ownership of Punjab & Sind Bank or Obligor or any other circumstance whatsoever which might otherwise constitute a discharge or defence of an indemnifier.
- 5) The obligations of the Obligor under this deed shall not be affected by any act, omission, matter or thing which, would reduce, release or prejudice the Obligor from any of the indemnified obligations under this indemnity or prejudice or diminish the indemnified obligations in whole or in part, including in law, equity or contract (whether or not known to it or to Punjab & Sind Bank).
- 6) This indemnity shall survive the Contract.
- 7) Any notice, request or other communication to be given or made under this indemnity shall be in writing addressed to either party at the address stated in the Contract and/or as stated above.
- 8) This indemnity and other non-contractual obligations arising out of this indemnity, shall be governed by, and construed in accordance with, the laws of India. The Obligor irrevocably and unconditionally agrees that any legal action, suit or proceedings arising out of or relating to this indemnity may be brought in the Courts/Tribunals at **Varanasi**. Final judgment against the Obligor in any such action, suit or proceeding shall be conclusive and may be end in any other jurisdiction, by suit on the judgment, a certified copy of which shall be conclusive evidence of the judgment, or in any other manner provided by law. By the execution of this indemnity, the Obligor irrevocably submits to the exclusive jurisdiction of such Court/Tribunal in any such action, suit or proceeding.

9) Punjab & Sind Bank may assign or transfer all or any part of its interest herein to any other person. Obligor shall not assign or transfer any of its rights or obligations under this indemnity, except with the prior written consent of Punjab & Sind Bank.

IN WITNESS WHEREOF, the Obligor has signed these presents on the day, month and year first above written.

Signed, sealed and delivered by the said service provider, _____ to
_____ (Name of the Bank) _____

4. Tender documents containing Notice to the Contractors, Conditions of Contract, Appendix thereto, Special Conditions of contract, Specifications, Schedule of Quantities with the rates entered therein shall be read and studied as forming part of this agreement, and the parties hereto shall respectively abide by and submit themselves to the conditions, stipulations and perform the agreements on their parts respectively in such conditions contained.

5. Time shall be considered as of the essence of this Agreement and the Contractor hereby agrees to commence the work soon after the site is handed over to him as provided for in the said conditions and to complete the entire work within 20 Days from date of work order, nevertheless to the provisions of extension of time.

6. This agreement and Contract shall be deemed to have been made in and any question or dispute arising out of or in any way connected with this agreement and contract shall be deemed to have arisen in and only the courts in Bombay shall have jurisdiction on to determine the same.

AS WITNESS the hands of the said parties.

Signed by the said

In the presence of

Witness

Name:

Address:

BANK

Signed by the said

In the presence of

Witness

Name:

Address:

CONTRACTOR

UNDERTAKING FOR PRE-CONTRACT INTEGRITY PACT

The REGIONAL Manager,
Punjab and Sind Bank,
REGIONAL Office Varanasi,
Shivpur
Varanasi (Uttar Pradesh) - 221 003

Dear Sir,

INTEGRITY PACT

Subject: E-TENDER FOR CIVIL WORK, INTERIOR FURNISHING, ELECTRICAL WORKS, FIRE ALARM SYSTEM & AIR CONDITIONING WORKS OF PUNJAB & SIND BANK BRANCH OFFICE- RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP-221712.

I/We acknowledge that Punjab & Sind Bank is committed to follow the principle of transparency equity and competitiveness as enumerated in the Integrity Agreement enclosed with the tender/bid document. I/We agree that the Notice Inviting Tender (NIT) is an invitation to offer made on the condition that I/We will sign the enclosed integrity Agreement, which is an integral part of tender documents, failing which I/We will stand disqualified from the tendering process. I/We acknowledge that **THE MAKING OF THE BID SHALL BE REGARDED AS AN UNCONDITIONAL AND ABSOLUTE ACCEPTANCE** of this condition of the NIT.

I/We confirm acceptance and compliance with the Integrity Agreement in letter and spirit and further agree that execution of the said Integrity Agreement shall be separate and distinct from the main contract, which will come into existence when Punjab & Sind Bank finally accepts tender/bid. I/We acknowledge and accept the duration of the Integrity Agreement, which shall be in the line with Article 6 of the enclosed Integrity Agreement.

I/We acknowledge that in the event of my/our failure to sign and accept the Integrity Agreement, while submitting the tender/bid, Punjab & Sind Bank shall have unqualified, absolute and unfettered right to disqualify the tenderer/bidder and reject the tender/bid in accordance with terms and conditions of the tender/bid.

Yours faithfully

(Duly authorized signatory of the Bidder)

To be signed by the bidder and same signatory competent / authorized to sign the relevant contract on behalf of Bidder.

PRE CONTRACT INTEGRITY PACT (On bidder's letterhead)

Between

Punjab & Sind Bank (PSB) hereinafter referred to as "**The Principal**",

And

_____ hereinafter referred to as "**The Bidder/ Contractor**"

Preamble

The Principal intends to award, under laid down organizational procedures, contract/ s for civil work, interior furnishing, fire alarm system & air conditioning works of PUNJAB & SIND BANK BRANCH OFFICE- RASRA – ADDRESS- CHHITUANI ANDAR PARAGANA LAKHNESHWAR TEH-RASRA DIST- BALIA UP- 221712.

the Principal values full compliance with all relevant laws of the land, rules, regulations, economic use of resources and of fairness / transparency in its relations with its Bidder(s) and /or Contractor(s).

In order to achieve these goals, the Principal has appointed Independent External Monitors (IEMs) who will monitor the tender process and the execution of the contract for compliance with the principles mentioned above.

Section 1 - Commitments of the Principal

- (1) The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles: -
 - a. No employee of the Principal, personally or through family members, will in connection with the tender for, or the execution of a contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.
 - b. The Principal will, during the tender process treat all Bidder(s) with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential / additional information through which the Bidder(s) could obtain an advantage in relation to the tender process or the contract execution.
 - c. The Principal will exclude from the process all known prejudiced persons.
- (2) If the Principal obtains information on the conduct of any of its employees which is a criminal offence under the IPC/PC Act, or if there be a substantive suspicion in this regard, the Principal will inform the Chief Vigilance Officer and in addition can initiate disciplinary actions.

Section 2 - Commitments of the Bidder(s)/ Contractor(s)

(1) The Bidder(s)/ Contractor(s) commit themselves to take all measures necessary to prevent corruption. The Bidder(s)/ Contractor(s) commit themselves to observe the following principles during participation in the tender process and during the contract execution.

a) The Bidder(s)/ Contractor(s) will not, directly or through any other person or firm, offer, promise or give to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material or other benefit which he/she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.

b) The Bidder(s)/ Contractor(s) will not enter with other Bidders into any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the bidding process.

c) The Bidder(s)/ Contractor(s) will not commit any offence under the relevant IPC/PC Act; further the Bidder(s)/ Contractor(s) will not use improperly, for purposes of competition or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.

d) The Bidder(s)/Contractor(s) of foreign origin shall disclose the name and address of the Agents/representatives in India, if any similarly the Bidder(s)/Contractor(s) of Indian Nationality shall furnish the name and address of the foreign principals, if any. Further details as mentioned in the "Guidelines on Indian Agents of Foreign Suppliers" shall be disclosed by the Bidder(s)/Contractor(s). Further, as mentioned in the Guidelines all the payments made to the Indian agent/representative have to be in Indian Rupees only.

e) The Bidder(s)/ Contractor(s) will, when presenting their bid, disclose any and all payments made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the contract.

f) Bidder(s) /Contractor(s) who have signed the Integrity Pact shall not approach the Courts while representing the matter to IEMs and shall wait for their decision in the matter.

(2) The Bidder(s)/ Contractor(s) will not instigate third persons to commit offences outlined above or be an accessory to such offences.

Section 3 - Disqualification from tender process and exclusion from future contracts

If the Bidder(s)/Contractor(s), before award or during execution has committed a transgression through a violation of Section 2, above or in any other form such as to put their reliability or credibility in question, the Principal is entitled to disqualify the Bidder(s)/Contractor(s) from the tender process or take action as per the procedure mentioned in the "Guidelines on Banning of business dealings".

Section 4 - Compensation for Damages

(1) If the Principal has disqualified the Bidder(s) from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover the damages equivalent to Earnest Money Deposit/ Bid Security.

(2) If the Principal has terminated the contract according to Section 3, or if the Principal is entitled to terminate the contract according to Section 3, the Principal shall be entitled to demand and recover from the Contractor liquidated damages of the Contract value or the amount equivalent to Performance Bank Guarantee.

Section 5 - Previous transgression

(1) The Bidder declares that no previous transgressions occurred in the last three years with any other Company in any country conforming to the anti-corruption approach or with any Public Sector Enterprise in India that could justify his exclusion from the tender process.

(2) If the Bidder makes incorrect statement on this subject, he can be disqualified from the tender process or action can be taken as per the procedure mentioned in "Guidelines on Banning of business dealings".

Section 6 - Equal treatment of all Bidders / Contractors / Subcontractors

(1) In case of Sub-contracting, the Principal Contractor shall take the responsibility of the adoption of Integrity Pact by the Sub-contractor.

(2) The Principal will enter into agreements with identical conditions as this one with all Bidders and Contractors.

(3) The Principal will disqualify from the tender process all bidders who do not sign this Pact or violate its provisions.

Section 7 - Criminal charges against violating Bidder(s)/Contractor(s) /Subcontractor(s)

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Subcontractor, or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor which constitutes corruption, or if the Principal has substantive suspicion in this regard, the Principal will inform the same to the Chief Vigilance Officer.

Section 8 - Independent External Monitor

The Punjab & Sind Bank has appointed the following Independent External Monitors (IEM) as per Central Vigilance Commission guidelines. Name and addresses of the Monitors are given below:

1. Sh. Debal Kumar Gayen , E-mail: - gayen.dk@gmail.com, Phone No.- 9831268698

2. Sh. Parmod Kuymar Garg, E-mail: - pkgarg.1957@gmail.com, Phone No.-9810778058

(1) The task of IEM is to review independently and objectively, whether and to what extent the parties comply with the obligations under this agreement.

(2) The IEM is not subject to instructions by the representatives of the parties and performs his/her functions neutrally and independently. The IEM would have access to all Contract documents, whenever required. It will be obligatory for him / her to treat the information and documents of the Bidders/Contractors as confidential. He/ she reports to the MD & CEO, Punjab & Sind Bank.

(3) The Bidder(s)/Contractor(s) accepts that the IEM has the right to access without restriction to all Project documentation of the Principal including that provided by the Contractor. The Contractor will also grant the IEM, upon his/her request and demonstration of a valid interest, unrestricted and unconditional access to their project documentation. The same is applicable to Sub-contractors.

(4) The Monitor is under contractual obligation to treat the information and documents of the Bidder(s)/ Contractor(s)/ Sub-contractor(s) with confidentiality. The Monitor has also signed declarations on Non-Disclosure of Confidential Information' and of 'Absence of Conflict of Interest'. In case of any conflict of interest arising at a later date, the IEM shall inform MD & CEO, Punjab & Sind Bank and recuse himself/ herself from that case.

(5) The Bank will provide to the IEM sufficient information about all meetings among the parties related to the Project provided such meetings could have an impact on the contractual relations between the Bank and the Contractor. The parties offer to the IEM the option to participate in such meetings.

(6) As soon as the IEM notices, or believes to notice, a violation of this agreement, he/she will so inform the Management of the Bank and request the Management to discontinue or take corrective action, or to take other relevant action. The IEM can in this regard submit nonbinding recommendations. Beyond this, the IEM has no right to demand from the parties that they act in a specific manner, refrain from action or tolerate action.

(7) The IEM will submit a written report to the MD & CEO, Punjab & Sind Bank within 8 to 10 weeks from the date of reference or intimation to him by the Bank and, should the occasion arise, submit proposals for correcting problematic situations.

(8) If the IEM has reported to the MD & CEO, Punjab & Sind Bank, a substantiated suspicion of an offence under relevant IPC/ PC Act, and the MD & CEO, Punjab & Sind Bank has not, within the reasonable time taken visible action to proceed against such offence or reported it to the Chief Vigilance Officer, the IEM may also transmit this information directly to the Central Vigilance Commissioner.

(9) The word IEM would include both singular and plural.

Section 9- Pact Duration

This Pact begins when both parties have legally signed it. It expires for the Contractor 12 months after the last payment under the contract, and for all other Bidders 6 months after the contract has been awarded. Any violation of the same would entail disqualification of the bidders and exclusion from future business dealings.

If any claim is made / lodged during this time, the same shall be binding and continue to be valid despite the lapse of this pact as specified above, unless it is discharged / determined by the Competent Authority of the Punjab & Sind Bank.

Section 10 - Other provisions

(1) This agreement is subject to Indian Law. Place of performance and jurisdiction is the Registered Office of the Principal, i.e. New Delhi.

(2) Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.

(3) If the Contractor is a partnership or a consortium, this agreement must be signed by all partners or consortium members.

(4) Should one or several provisions of this agreement turn out to be invalid, the remainder of this agreement remains valid. In this case, the parties will strive to come to an agreement to their original intentions.

(5) Issues like Warranty / Guarantee etc. shall be outside the purview of IEMs.

(6) In the event of any contradiction between the Integrity Pact and its Annexure, the Clause in the Integrity Pact will prevail.

(For & On behalf of the Bank)

(For & On behalf of Bidder/ Contractor)

(Office Seal)

(Office Seal)

Place _____

Date _____

Witness 1: _____

(Name &Address)

Witness 2: _____

(Name &Address) _____

ANNEXURE A
SERVICE PROVIDERS PROFILE

S.No.	Information regarding	Details to be furnished by the Bidder
1)	Name & Address of the firm	
2)	PAN No.	
3)	Type of organization & year of Incorporation.	
4)	Correspondence address with contact person, name, telephone number, mobile number, E-mail etc.	
5)	Name & details of Directors/Partners/ Proprietor	
6)	Company Profile with year of establishment	
7)	Whether registered with Registrar of Companies, if so, number & date	
8)	Income Tax No.	
9)	GST No.	
10)	Names of the Bankers with address	1. 2. 3.
11)	Turnover of the company. Please provide the details for the last 5 years ending March 31, 2023. (Certified copies of audited/self-attested Balance financial year Sheet and profit & loss account statement to be enclosed) (in Lacs) (in INR)	2024-2025-Rs. 2023-2024-Rs. 2022-2023-Rs. 2021-2022-Rs. 2020-2021-Rs.
12)	Details of the work executed by the firm during last 5 Financial years (only those works to be mentioned that qualify the prequalification criteria). Copies of Satisfactory work certificate obtained from employers to be enclosed.	Annexure B to be filled up.

I/We confirm that to the best of our knowledge this information is authentic and accept that any deliberate concealment will amount to disqualification at any stage.

Seal and Signature of the Bidder/s.

Date:

Place:

LIST OF CONTRACTS EXECUTED DURING LAST 5 YEARS

S. No.	Name and address of client/employer client/ employer	Supervising Authority under whom the work was carried out (Name and Designation)	Work Order Ref No & Date	Contract Period	Contract Value (In Rs Lacs)	Copy of work order and Performance certificate enclosed	Remarks

Signature of the Bidder with Seal

ANNEXURE C
PAST PERFORMANCE

Names along with address and telephone numbers of two organization for whom work done in the past and who are in a position to certify the past performance of your firm

S.No.	Name of the employer	Address	Telephone Number/Mobile	Fax/E-mail

Signature of the Bidder with Seal

ANNEXURE D

ORGANIZATIONAL SET UP AND TRAINED MAN POWER AVAILABLE

S.No.	Name	Employee Code	Qualification	Experience	Works done	Employed with your firm since	Any other information

Signature of the Bidder with Seal

ANNEXURE E

Details of litigation / arbitration cases resulting from the contracts executed by your firm in the past or currently under execution

Year	Award for/Against Applicant	Name of Client	Cause of Litigation	Disputed Amount	Actual Award Amount

Signature of the Bidder with Seal

SPECIFICATIONS/BRAND NAMES OF CIVIL AND FURNISHING MATERIALS AND FINISHES

In case it is established that the brands specified below are not available in the market are subject to the approval of the alternative brand by the Architect

S. NO.	ITEM	COMPANY MAKE
1	REINFORCEMENT STEEL	TATA, SAIL, JINDAL
2	AAC BLOCK	BILT, MAGNA, ULTATECH OR LOCAL AVAILABLE
3	CEMENT	ORDINARY PORTLAND CEMENT 43 GRADE MANUFACTURED BY ACC/ ULTRA TECH/AMBUJA
4	POLYSULPHIDE SEALANT	PIDISEAL BY M/S PIDILITE INDUSTRIES LTD., FOSROC, SHALIMAR, ROFF
5	WATER PROOFING COMPOUND	CICO , FOSROC, DR FIXIT, ROFF
6	SHUTTERING PLYWOOD	GREEN, CENTURY, ARCHID
7	TOUGHENED GLASS	SAINT GOBIN OR EQUIVALENT
8	GLASS/LACQUERED GLASS	MODI FLOAT. ST. GOBAIN., ASAHI
9	WIRED GLASS	6MM THK. WIRED GLASS MANUFACTURED BY HINDUSTAN SAFETY GLASS WORKS LTD. CALCUTTA, OR VALLABH GLASS WORKS GUJRAT./HARYANA SHEET GLASS.
10	WHITE CEMENT	J.K. WHITE CEMENT , BIRLA WHITE CEMENT
11	DISTEMPER, PAINT	ENAMEL, PLASTIC EMULSION MANUFACTURED BY BERGER PAINTS, ASIAN PAINTS, NEROLAC , SHALIMAR PAINT, ICI.
12	PLASTER OF PARIS	SHRIRAM, SAKARNI, BIRLA,J.K
13	PUTTY	ASIAN PAINTS., JK, BIRLA
14	EXPANSION BOLTS FOR FIXING	DASH FASTENERS OF APPROPRIATE SIZE BY HILTI OR EQUIVALENT
15	WINDOW HARDWARE	HETTICH, KAFF, EBCO OR HAFFLE
16	CERAMIC TILES	JOHNSON,SOMANY,KAJARIA, VARMORA,
17	VINYL FLOOR	ARMSTRONG/ RIKVIN , WONDER FLOOR.
18	VITRIFIED TILES	JOHNSON, SOMANY, KAJARIA , VARMORA , SIMPOLO(WHITE BASE)
19	GLAZED TILES	JOHNSON , SOMANY, KAJARIA , VARMORA
20	SPECIAL CERAMIC TILES	SARASWATI CERAMICS, OTHER APPROVED POTTERY IN DELHI / KHURJA
21	HINGES AND DRAWER SLIDE, KEYBOARD	KAFF, HETTICH, OZONE, HAFFLE, EBCO
22	LOCKS, HANDLES	GODREJ, DORSET, DORMA, ASPA
23	DOOR CLOSERS, FLOOR SPRING, DOOR STOPPER AND HARDWARE FITTING	DORMA, DORSET, OZONE, GODREJ
24	ALUM, TOWER BOLTS, MAGNETIC CATCHER HARDWARE FITTING,	EBCO, EVERITE, SIGMA ,HETTICH, NIKON
25	MS SCREW	NETTLE FOLD, CALIBER, ARASNA, SUPERMAX
26	M.S. PIPES (RAILING)	JINDAL , APOLLO
27	FLUSH DOORS	DURO, CENTURY, GREENPLY, ARCHID
28	VENEER	DURO, CENTURY, GREEN

29	LAMINATE	GREENLAM, CENTURY, ARCHID
30	PLYWOOD, BLOCK BOARD ,	DURO, CENTURY, GREEN, ARCHID
31	STRUCTURAL STEEL	SAIL, TISCO, JINDAL.
32	TEXTURE TILES FOR FALSE CEILINGS / FIBER CEMENT BOARD	ARMSTRONG, EVEREST INDUSTRIES LTD.
33	WOOD	TEAK WOOD FIRST CLASS OF CP OR BURMA
34	M.S. ALUMINIUM LINEAL CEILING	INTERARCH, VISTA.
35	VENETIAL BLINDS	TRAC, VISTA, MAC, HUNTER DOUGLAS
36	GYPBOARD CEILING	GYPSUM INDIA, LAFAARZ., ST. GOBAIN
37	HEAT REFLECTIVE FILM	GARWARE, 3M, SUNBIRD, WISDOM
38	ADHESIVE	FEVICOL , MAHAKOL
39	TILE ADHESIVE	UNITILE, ROFF CHEMICALS, KAJARIA.
40	MIRROR	ATUL, JOLLY, MODI GUARD, ASAHI
41	G.I.PIPE AND FITTINGS	TATA, JINDAL, APOLLO, UNIK,
42	CENTRIFUGALLY CAST (SPUN) IRON SOIL WASTE & VENT PIPE & FITTINGS	JAYASWAL NECO (NAGPUR), C.I.A.L. (DURGAPUR)
43	WOOD PRESERVATIVE	WOOD GUARD OR APPROVED EQ/ICI.
44	ALUMINIUM COMPOSITE SHEET	ALUCOBOND, ALSTONE, EUROBOND.
45	ALUMINIUM SECTIONS	JINDAL, INDAL, HINDALCO.
46	C.I./R.W.P.	NECO, RIF, IIS OR EQ.
47	C.P BRASS FITTING	JAGUAR, PARKO ,PARRYWARE, GROHE, KOHLER
48	SANITARY WARE	HINDWARE, PARRYWARE, JAGUAR, GROHE, KOHLER
49	STAINLESS STEEL SINK	DIAMOND , NIRALI, JAYNA, NILKANTH,
50	SANITARY FITTINGS VISIBLE	JAGUAR, GROHE ,KOHLER, PARRYWARE
51	PVC,U.P.V.C PIPE	SUPREME, PRINCE, ASTRAL, FINOLEX
52	CI BRASS LA PIPES	ELECTRO STEEL, KESORAM
53	STONE WARE PIPES	BHASKAR, ANAND,
54	R.C.C PIPES	ISI MARKED OF APPROVED QUALITY
55	LOFT TANK	SYNTAX, UNIPLAS, PLOYION
56	CI PIPES & WORK	NECO, RIF,SIF,BIS OR EQUIVALENT ISI MAKE
57	ANTI TERMITE	THIDDAN (35 E.C.), DURSBAN – 20 TC, TRISHUL
58	GATE VALVES	LEADER, ZOLOTO
59	PLASTIC W.C SEAT COVER	COMMANDER, DIPLOMAT
60	GUN METAL VALVE (FULL WAY CHECK & GLEBE VALVES)	LEADER, SANT, ZOLOTO
61	C.I VALVE (FULL WAY CHECK & GLEBE VALVES	KIRLOSKAR, LEADER, ZOLOTO
62	CPVC	PRINCE, ASTRAL, FINOLEX , SUPREME,
63	READY MIX CONCRETE	ACC, ULTRATECH, RMC INDIA ,LAFARGE
64	ACRYLIC SOILD SURFACE THERMOFORMED	DUPONT,LG, AVONITE

In the event of the materials of makes called for are not available and alternative makes are approved (by the consultant) for incorporation in the work, the rates quoted shall be suitably amended based on the price variation between the specified makes and alternative makes on the day the alternative makes are accepted.

TENDER FOR FURNISHING WORKS FOR PUNJAB & SIND BANK, RASDA BRANCH, UTTAR PRADESH.

A	FURNISHING WORKS (BRANCH & ATM)							
S. No.	Description				Qty	Unit	Rate	Amount
1	FALSE CEILING (Including ATM Ceiling)							
	a.	Providing and fixing GYPSUM BOARD FALSE CEILING in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India/Saint -Gobain Gyproc and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel of size 20X27X30 mm and 0.55 mm thick for light fittings, AC Grills, diffusers, suspenders etc. shall be standard sections supplied by Gypsum India/ Saint Gobain. Spacing of intermediate channels shall be at 1200 mm c/c and ceiling section at 457 mm c/c. The work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade ICI/ ASHIAN PAINTS make, making cut-out for light fixtures /fittings, etc. The Final coat shall be done with FOAM ROLLER and no brush marks should be visible. Providing of perimeter channels / beading etc. as per drawing complete in all respects.(All measurement in sqft only and finished surface area shall be measured)			785	sqft		
	b.	GRID FALSE CEILING(24" x 24")						
		24"x24" Grid False Ceiling Providing and fixing in the true horizontal level false ceiling system of Armstrong world industries. The suspension system shall be the Armstrong Trulock Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color black or white revealed Silhouette main runners and cross tees to have mitered ends with birds mouth notches to provide mitered cruciform junctions. Main runners to be spaced at 12mm c/c fixed by using 2mm pre straightened GI Wire.Main tee,rotary stitched of size 15mm x44mmx3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mmx44mm x1200mm at every 600 mm c/c maximum and 600 mm c/c cross tee of size 15 mm x 44 mm x 600 mm at every 1200mm c/c maximum and 19mmx19mmx3000 wall angle. All as per the design and instructions Architects (make- Armstrong & thikness of tile- 16 mm)			647	sqft		
2	PARTITIONS							
	a	Low height Partition Providing & fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved shade. Till the height of 3'-3" and 1'-3"(10mm thk.) toughened glass on (side & front) top complete with teak beading, The PU polishing teak sections of approved shade as per drawing and fixing of soft board covering with similer fabric. Complete in all respects to the complete satisfaction of the Architect.			52	sqft		
	b	Full height Partition Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved Make and shade. minimum 8 mm thick toughened glass of approved make with etching/taping as required) on the glazed portion. The work includes PU polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks.			483	sqft		
	b1	Full height Partition Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 12 mm BISON BOARD of approved make on both faces finished with 1mm thick laminate of approved Make and shade. minimum 8 mm thick toughened glass of approved make with etching/taping as required) on the glazed portion. The work includes spirit polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks.			150	sqft		
	c	SEMI GLAZED PATITION Providing & fixing of partly glazed (12mm toughened glass of approved make as per design), made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of Approved Make on both faces finished with 1mm thick laminate of approved make & shade The work includes providing PU polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks. Complete in all respects to the complete satisfaction of the Architect./Engineer.			286	sqft		
	d	Cash Cabin front Partition With 12 mm toughened Glass including fixing. Complete in all respect.			18	sqft		

	e	Providing and fixing 1.5/ 2 x 4/5 feet bevelled 12 mm toughened Glass on all tables /counters complete as per drawing including glass support. Glass has to fixed as vertical partition in the front end of the counter (towards customer side) to restrict direct access of customer	28	sqft		
	f	Providing and fixing of following items/ accessories completeed in all including				
	(i)	Knight latch for cash cabin door.(Make Godrej)	1	no.		
	(ii)	Mortise locks with handles.(Make Godrej)	6	no.		
	(iii)	Hydraulic Door closer.(Make Godrej/ Universal)	6	no.		
	(iv)	Floor springs.for Glass door.(Make Godrej/ Universal)	0	no.		
3		GLASS DOORS (BM, ATM & MAIN ENTRANCE)				
	A	Providing and fixing of (3'-0"/ 3'-6" X8'-0")12mm toughened glass door with18" long SS handles, floor spring (Ozone-FS- 9400) etc, locking arrangement of brass make at top of standard make(patch fitting), including fixing of Frosted strip vision film & bank logo as directed by the Bank/ Architects.	73	sqft		
	B	FIXED GLAZING Providing and fixing external FIXED GLAZING comprising of 12 mm thick toughened glass of approved Make with top, bottom and vertical U Channel frames comprising of powder coated (shade as approved) 16 gauge Aluminium members of approved shade 1.5mm avg. thick top, bottom & vertical member with clip sections as per specifications and drawings to complete satisfaction of the Architect.	107	sqft		
	C	BLOCK DOORS Providing and fixing solid core 38 mm solid core flush door finished with lippings in all side with necessary door hinges , cylindrical locks(golden, Godrej) , door clouser, door stoppers, etc with a frame work of T.W./Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished,edges to be finished with wooden lippings.A wooden moulding size 1.5"x2/8" to be provided all along the periferi of the frame work in the both sides . All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8 mm thk etched toughened glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary mouldings.				
	a	Partly glazed door with out etching & frosting				
	i	(2'-6"/3'-0"x7'-0") for PASSAGE Door & Record Room	146	sqft		
	b	Blocked doors				
	i	(2'-6"/3'-0"x7'-0") for Toilets, Pantry & UPS doors	23	sqft		
4		COUNTERS AND TABLES				
	a	Providing and fixing Manager Table with 10mm beveled toughened glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing, made up of 19mm board of approved Make and finished with 1 mm thick laminate of approved make, and shade. Table(with one side drawer unit and another side drawer unit) shall be provided with drawers sliding on telescopic channels and one cabinet with proper locking arrangements and keyboard with telescopic channels . The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, PU polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces to be finished with 0.8mm thik laminate of approved shade. complete in all respects to the entire satisfaction of the Architect/Bank.				
		Table size: 5'-6" / 6'-0" x 3'-0 x 2'-6"	1	no.		
	b	SIDE CREDENZAS				
		Providing and fixing SIDE CREDENZAS size 3'-0" to 4'-0" x 1'-3" x 2'-6" made of 19mm board of approved make finished with 1 mm thick laminate of approved Make and shade on top , back, sides and front having two drawers and cabinet below complete with all accessories like locks, handles, megnetic catcher etc. Teak wood beading on all exposed edges with PU polish. (Should not be attahced with partitions)	1	no.		

	d	WORK STATIONS TABLE Providing and fixing of COMPUTER work Stations as per layout plan and and 10mm beveled Toughened glass of approved make to be fitted on top obtain the total height of 2'-6" high working top (As per drawing) made up of 19mm board / ply of approved Make, finished with 1 mm thick laminate of approved Make, shade as approved as per the detailed drawing . The tables shall have as per approved shade and color. All exposed surfaces (such as counter front, sides, drawers and cupboard etc) must be finished with 1mm thick laminate of approved make. Table top shall be finished with 1mm thick laminate. The inner exposed surfaces to be painted over one coat of primer and enamel paint of approved shade. Each unit of table shall be provided with keyboard tray with telescopic channels. The work includes fixing of wire managers, locks, footrests, PU polishing the steam beach beading, lipping, exposed frame, etc. as per drawings, and The inner exposed surfaces shall be finished with 0.8mm thik laminate of approved shade. complete in all respects to the complete satisfaction of the Architect/Bank.				
	a	Officers Table (5'-0"/5'-6" x 2'-6 x 2'-6") on top of table 10mm thk beveled toughened glass.	0	nos		
	b	Officers Table/ staff tables (4'-0"/4'-6" x 2'-6" x 2'-6") additionl (Daftri & guard's Tables)	3	nos		
	c	CASH COUNTER WITH TOP UP ALUMINIUM GRILL Providing and fixing of CASH COUNTER 2'-6"/3'-9" high made up of 19mm board/ply of approved make and finished with 1 mm thick laminate of make, shade as approved and as per detailed drawing. 2'-6' wide working table top, key board tray, drawer with telescopic channels (TOP DRAWER SHOULD BE DIVIDED INTO SECTIONS SO AS TO PILE DIFFERENT CURRENCY NOTES SEPERATELY) and cupboard with fixing of soft board with similer fabric. All exposed surfaces (such as counter front, sides, drawers and cupboard etc) to be finished with 1mm thick laminate of approved make. The inner exposed surfaces shall be finished with 0.8mm thik laminate of off white shade. The work includes fixing of furniture locks, wire managers, PU polish of steam beach wood beading/ lipping etc.complete in all respects to the entire satisfaction of Architect. Transaction top should be minimum 18" and (4'-5"/ 5' -0" Average Length) and fixing of aluminium grill on top of cash counter spacing of grill 75mm & thikness of grill 5/6 mm.	1	nos		
5		MISCELLANEOUS FURNITURE				
	a	Providing & fixing STORAGE CABINETS indipendent units (movable) 12 feet long (maximum) 4'-6" ht and 1'-6" deep as per layout plan made up of 19mm board/ply of approved make and finished with 1mm thick laminate of approved make, shade and as per detailed drawing. one shelves made up of 19mm thick board, each drawer(with lock) & cabinet(with lock) 19mm thickness portion every place must be finished with proper lipping/ margin teak wood finish. In side and back shall be finished with 0.8mm thick laminate of approved Make and color The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc as specified. complete in all respects.				
	b	Full height STORAGE CABINATES upto 8'-6" false ceiling hight specification as per (a)	321	Sqft		
	c	Half height STORAGE CABINATES upto 4'-0" / 2'-6" hight specification as per (a)	188	Sqft		
	f	COLUMN / WALL PANNELING Providing and fixing of COLUMN PANNELING as per design, consisting of 10 mm thick MDF BOARD of approved Make fixed on wall with made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways. The above shall be laminated with 1mm thick mica of approved Make, The work includes PU polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	967	sqft		
7		NOTICE BOARD				
		Providing and fixing soft board with glass White board necessary framework and 12mm bwp plywood on top 12MM jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi.The work to be completed as per approval and satisfaction of the Architect.	6	Sft		
8		ACP WALL PANELLING				
		Providing & Fixing ACP sheet (4 MM THK) panelling with 2 1/2" x 1 1/2" Aluminium (16 gauge) framework at 2'-0" c/c fixed over the existing wall/ partitions. Approved Make- ALUCOBOND/ ALUDECOR	213	Sft		
9		WRITING LEDGE Providing and fixing writing ledge as per design made out 19mm comm. board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. ply to be made on top of the writing ledge finished with 1.0 mm laminate, inside 0.8 mm laminates .The work to be completed as per design and approval of the architect.	1	no.		

10	SUGGESTION BOX Providing and fixing Suggestion box as per design made out 19mm comm. board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. ply to be made on top of the writing ledge finished with 1.0 mm laminate, inside 0.8 mm laminate .The work to be completed as per design and approval of the architect.	1	no.		
11	CHEQUE DEPOSIT BOX Providing and fixing Suggestion box as per design made out 19mm comm. board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. ply to be made on top of the writing ledge finished with 1.0 mm laminate, inside 0.8 mm laminate .The work to be completed as per design and approval of the architect.	1	no.		
12	WICKET GATE Providing and fixing 4' - 0' ht. WICKET GATE between the counters to check the movements of customers inside the restricted area. Fully paneled door shutter including the door frame made up of styles and top rail, bottom rail using 1st class hardwood, 9mm ply of approved Make to be fixed on both faces finished with 1 mm thick laminate of approved Make. The work includes providing and fixing necessary hardware SS finish latches, butt hinges etc., steam beach beading etc. (PU polished) as per drawings to the full satisfaction of the Architect, complete in all respects.	1	no.		
13	CENTER TABLES (3'-0" X 2'-0" X 1'-6"HT) Providing and making center tables of above mentioned size as per drg. Table top shall consist of 12 mm. Thk.float glass with champhered edge with approved quality etching. The base shall be made up of Teak wood frame as directed by the Architect. All exposed faces finished with natural PU polish . All inner surfaces will be finished with natural french polish.	1	no.		
14	Frosted Film -Providing & pasting frosted film (3M, Garware make) on glass work partition and glass door as required as directed by the consultant/Architect.	25	Sft		
15	Supplying , fabricating and installation of "PUNJAB & SIND BANK" made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings. This Coloured Acrylic sheet box logo should be fixed with light from inside so as to have a back lit , as per the direction of the architect.	1	no.		
16	Providing oviding and fixing panelling on wall & ceilings with WPC (Wood Polymer Composite) Fluted Panels of size 2950MM (LENGTH)X 195MM (WIDTH) X 27MM(HEIGHT) of LEBEN/ Alutuff / Murrato or other approved make of approved shade in approved pattern as directed by the architect. Rates shall be inclusive of all hardware fittings and fixtures as required to fix the same on the wall and ceilings including corner beading and fastners & complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	175	Sft		
17	Supply and Installation of a 25-liter capacity, single-tap water cooler (often associated with brands like Voltas, Blue Star, or Usha) entails specific. Technical specifications.Capacity: 25 Ltr Storage / 25 Ltr Cooling (nominal). Body Material: Full Stainless Steel (SS) 304 Grade for the inner tank and SS 202/304 for the outer body to ensure corrosion resistance. Taps/Faucets: 01 No. (Single Tap). Refrigerant: Eco-friendly (Non-CFC) R-134A or R-290. Compressor: Hermetically sealed, high-efficiency rotary or reciprocating compressor. Warranty: Minimum 1-year comprehensive warranty on the machine and 3-5 years on the compressor. Installation: Installation of the unit at the designated site, including placing it on a level, stable floor. Connections: Providing all necessary inlet/outlet plumbing connections (1/2 inch BSP) and electrical connections. Commissioning: Testing for proper water pressure, cooling performance, and drainage. Power Supply: 230V ± 10%, 50Hz, Single Phase A.C. Insulation: High-density PUF (Polyurethane Foam) insulation to maintain temperature and save energy. Temperature Range: Typically 10°C to 25°C, or adjustable via thermostat. Drain Tray: Stainless steel drain tray with PVC/metallic drain pipe. Certification: BIS certification as per IS:1475 (Part-1) Model & brand approved by Architect.	1	No		
18	Supply & Insttaltion of Mini Refrigerator with Freezer, Direct Cool (45 Liter & 2-star) Blue star/ Samsung. Model & brand approved by Architect.	1	No		
19	Supply & Insttaltion of Stainless Steel Electric Food Display Hot Case – Rectangular Design, 2500 ml Capacity Food Warmer & Display Case- Special 5 Year Warranty & Model & brand approved by Architect.	1	No		
20	Supply & Insttaltion of Philips-Viva Collection HD4928/01 2100-Watt Induction Cooktop (Black)	1	No		

21	<p>Providing & fixing of GLOW SIGN BOARD SIZE- 17-0"X 4'-0" - Glow Sign Board Specifications The Glow Sign Boards shall be supplied using the following approved materials and components: 1- Vinyl & Flex: a-3M / Avery 4500 Series / LG 4000 Series translucent vinyl b- 3M / Avery / LG Backlit Flex (minimum 16-18 ounce) 2-Lighting Components: a- LED sign-rated tubes of reputed make (e.g. LEDMyplace, Westgate, RAB Lighting, SATCO/ NUVO, EIKO etc.) b- Auto Timer of reputed make (e.g. ELEQUA, Frontier, LEYDEN etc.) 3-Other Components: a- Pre-coated painted panels b- Make of electric wire: Polycab, Havells, RR Ind. c- 18 Gauge MS square pipe (double-sided frame) d- 3-piece iron bracket e- Complete fitting and transportation A comprehensive warranty of 3 years shall be provided for each Glow Sign Board. colour code and letter sizes provided by Bank. The work to be completed as per approval of the Bank.</p>	70	Sqft		
22	Supply & Installation of KENT Elegant RO Water Purifier 4 Years Free Service ISI Marked Multiple Purification Process RO + UF + TDS Control + UV LED Tank/ 8L Tank /15 LPH Flow. The work to be completed as per approval of the Bank.	1	No		
23	Indoor Plants- Supplying of indoor plants with ceramic pots & sizes are- 9" to 1'-0". The work to be completed as per approval of the Bank.	1	Lot		
	i Dypsis lutescens - Bamboo palm/ Areca palm				
	ii Raphis excelsa - Lady Palm				
	iii Ficus elastica - Rubber Plant				
	iv Spathiphyllum wallisii - Peace Lily				
	v Chlorophytum comosum - Spider Plant				
	vi Gerbera daisy - Daisy plant				
	vii Epiremnum aureum - Money plant				
	viii Epipremnum aureum syn. Scindapsus aureus - Golden Pothos				
	ix P. cordatum, P.scandens or P. selloum - Philodendron				
	x Gerbera Jamesonii - Gerbera Daisy				
	GRAND TOTAL				
	GST extra as applicable				

RECOMMENDED MAKE TO BE USED			
SR.	DESCRIPTION	MAKE / BRANDS	
1	MDF. (Medium Density Fibre Board) – CONFIRMING TO IS : 12406 - 2003. (Density: 750 – 850 Kgs/m3) colour code follow as per Bank Norms.	CENTURY/GREENPLY/ DURO/ NATIONAL	
2	PLYWOOD – BWP (Boiling Water Resistant, Termite Resistant & Borer Resistant) – CONFIRMING TO IS: 303.	CENTURY/GREENPLY/ DURO/ NATIONAL	
3	BLOCK BOARD – CONFIRMING TO IS : 11255 - 2003.	CENTURY/GREENPLY/ DURO/ NATIONAL	
4	FLUSH DOOR – CONFIRMING TO IS : 2202 (Part – 1) – 1991.	CENTURY/GREENPLY/ DURO/ NATIONAL	
5	LAMINATE – CONFIRMING TO IS : 2046-1995.	CENTURY/GREENLAM/ AICA-SUNMICA	
6	Lipping & Moulding	First Class Teak Wood	
7	Gypsum ceiling	Gypsum India, Saint - Gobain Gyproc india	
8	Grid Ceiling	Armstrong, Dexune	
9	GI Support system for False Ceiling	GYPSTEEL ULTRA	
10	Adhesive	Fevicol SH.	
11	Locks/Handles & all other hardware	OZONE/Dorma/ Godrej	
12	Glass	Modi/Asahi(Tata),Saint Gobain	
13	Aluminium	Jindal/ Hindalco/ NALCO	
14	Door Closer	OZONE/Dorma/ Godrej	
15	FLOOR SPRING	OZONE/Dorma /Godrej)	
	Vertical Blinds	Vista	
16	Paint	Nerolac / Asian Paints	
17	Wood Preservative	Bison by British Paints / Termiseal by ICI	
18	Cement	ACC / Ambuja/Birla Plus	
19	Preservative	Solignum/Black Japan / Termiseal	
20	Sanitary Fittings	Kohler / Hindware	
21	CP fittings	Jaguar	
22	GI pipe	Jindal/Bhushan	
23	Floor & Wall tiles	Nitco/Kajaria	
24	Overhead Water tank	Sintex	

NOTE:
1- The contractor is strictly advised to use the makes specified/approved by the Bank/Architect, unspecified items will not be paid until they are changed with the specified ones.
2- The Plywood used for the work shall be BWR (Boiling water proof range) confirming to IS 303.

Place:

Date: **Signature of contractor with seal**

BILL OF QUANTITY FOR ELECTRICAL WORK FOR PUNJAB & SIND BANK, RASDA BRANCH, UTTAR PRADESH.

ELECTRICAL WORKS (BRANCH + ATM)

S.No.	DESCRIPTION OF WORKS	UNIT	QTY	RATE	AMOUNT
1	<p>Light Primary Points in PVC Conduit - Point Wiring for light points, controlled through modular switches complete with PVC boxes & cover plate - The point wiring shall be done with 3x 1.5 sq.mm Fire Resistant Low smoke Low Halogen stranded Cu. Wire in PVC conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with PVC box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. Circuit wiring to be included in the point wiring rates. The circuit wiring starts from DB to point control box/ switch box using Fire Resistant Low smoke Low Halogen stranded Cu. Wire 2x2.5 sqmm & 1x2.5 sqmm earthing (min size) in 20/25/32 mm PVC conduit. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge</p>	Each	45		
2	<p>Light Secondary Points PVC Conduit - Point Wiring for light points interlooped from the primary point. The secondary point wiring shall be done with 3x 1.5 sq.mm FRLSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with MS box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge</p>	Each	25		
3	<p>5/6A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed /recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	12		
4	<p>5/6A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearby point through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No. 6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	3		

5	<p>UPS Primary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	10		
---	--	------	----	--	--

6	<p>UPS secondary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire looped from nearest UPS point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No., 6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	2		
7	<p>15/16A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No., 16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed /recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	8		
8	<p>15/16A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearest power point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No.,16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/ recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	2		
9	<p>AC point in PVC Conduit:- Supply & Installation of point wiring for Air Conditioner on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 20/25A , 3/5 pin sockets & 1 No. Single module 20/25A MCB, 1 Nos 25A Motor starter switch wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	6		
10	<p>Supply and laying 20 mm PVC conduit (MHS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.</p>	RM	30		

11	Supply and laying 25 mm PVC conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	35		
12	3x6 sq mm submains wiring in PVC conduit:- Supply and laying of 2x6 sq mm + 1x6 sq mm FR LSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	45		
13	Supply and laying of 3x10 submains wiring in PVC conduit Supply and laying of 2x10 sq mm + 1x10 sq mm FR (Fire Resistant) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	35		
14	Supply and laying of 4x10 flexible wire in PVC Conduit Supply and laying of 3x10 sq mm + 1x10 sq mm FR (Fire Resistant) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	15		
15	Supply installation testing and commissioning of 4 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with 2 Nos 63A DP MCB for Single Phase UPS input and output isolation	Set	3		
16	SITC of 12 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) i/c 1 Nos 63A DP MCB o/g 10 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	2		
17	SITC of 4 way Horizontal DB flush mounted on wall, sheet metal fabricated, powder coated, having dust- proof and vermin'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with i/c 1 Nos 63A TPN MCB o/g 12 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	3		
18	SITC of 4 way VTPN MCCB DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears (Double door VerticalL DB) with i/c 1 Nos 63A TPN MCCB Thermal Magnetic Release Adjustable overload: 0.8-1.0 x In Adjustable Short Circuit: 6-10 x In o/g 12 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	0		
19	SITC OF LT PANEL AS UNDER: (Manufacturrer must be approved from CPRI) Construction: Free Standing with front access, Dust & vermin Proof, Form 3b construction. Supply: 415V, 3Phase, 4 Wire, 50 Hz. Control Supply: 230V Single Phase Fault Level: 36KA for 1 Sec Fabrication: CRCA Sheet 14SWG for Gland Plate, Load Bearing Structure and Body, 16 SWG for partitions, doors and panels. 25x3 mm neoprene gasket for door, cover and gland plate. 40x5 mm gasket for joints and canopy. DC Locks to be provided on doors, danger plates on front and rear of bus bar chambers, live parts. Cable Entry / Exit : From top. Name plate: COPPER Powder Coating: Pre treated with 7 tank process and duly powder coated. TPN Busbars: 150A Rated copeer current density 1A/sq mm) with colour coded heat shrinkable sleeve. Neutral Bar of halfsize of Phase. Earth Bar of suitable size to be provided with earthing terminal on both ends Separate bus bar system to be provided for Emergency and Non Emergency supply outgoing Instrumentation: 1 Set 3 nos phase indicating lamps each backed up with MCB and switch shall be provided for each incomer. 1 no. VAF meter 0-200A with CT, selector switch, and fuse as reqd. Main Incomer- 125A MCCB Change Over - 1No. 100A Manual Changeover & 1 No. 63 A Automatic changeover for UPS Non Emergency Outgoing - 1 Nos 63A MCCB Emergency Outgoing 2 Nos 63A MCCB, 2 Nos 63A FP MCB, 4 Nos 40A DP MCB One Section in outgoing section in both emergency and non emergency section be kept spare for future provisions	Set	1		

20	SITC of 200Amp Kit kat Fuse unit 3 nos with 200 Amp neutral link on wooden board (3' x 3') complete with connections (new).	Set	1		
21	S & I of earth pit comprising of 600mm x 600mm 3mm. thick copper plate buried at a minimum depth of 2.7 meter including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	0		
22	S & I of earth pit comprising of G.I. earth pipe 4.5 metre long, 40 mm dia including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	3		
23	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required complete with insulation sleeve	RM	0		
24	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required complete with insulation sleeve	RM	0		
25	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface recessed conduit / submain wiring / cable as required.	RM	0		
26	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing along with existing surface / recessed conduit submain wiring / cable as required	RM	25		
27	Telephone point primary in PVC conduit: Supply & fixing on wall/ furniture/ partition recessed type modular telephone socket outlet (RJ-11) with mounting box & front plate complete with chase cutting, mending good etc. as required complete including Supply & laying of 1 pair 0.5 mm dia. PVC insulated unarmoured telephone cables through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement drawn from telephone tag block. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.	Each	3		
28	Providing, laying and connecting PVC insulated copper telephone cable of following sizes including termination in approved manner. 20-pair telephone cable.	RM	15		
29	Providing and fixing of telephone tag block (Krone type) of 50 pair housed in GI box with cover of suitable size including termination	Each	1		
30	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3x6 sq mm armoured aluminium cable in existing pipe / cable tray	RM	30		
31	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x50 armoured aluminium cable in existing pipe / cable tray	RM	45		
32	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x35 armoured aluminium cable in existing pipe / cable tray	RM	25		
33	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x70 aluminium armoured cable	SET	0		
34	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x50 aluminium armoured cable	SET	12		
35	Supply, Installation, testing and commissioning of 2'X2' Recessed type LED LIGHT FITTINGS of 33-36 W with minimum lumen level of 3900 lumens, CRCA / Extruded aluminium housing, efficiency of 120 lumens per watt and & Average life not less than 50000 hrs. The light should be hanged/supported by MS chain from ceiling directly and not be kept directly on false ceiling frame. Cutting of ceiling, framing etc. be included in the costs. Standard warranty of light fittings shall be minimum 2 years.	Each	11		
36	Supply, Installation, testing and commissioning of LED DOWNLIGHT FITTINGS of 15-18 W with minimum lumen level of 1650 lumens with die cast aluminium, efficiency of 110 lumens per watt and & Average life not less than 30000 hrs. Cutting of ceiling, modifications required to the ceiling be included in the cost. Standard warranty of light fittings shall be minimum 2 years.	Each	24		

37	Supply Installation testing and commissioning of 4 ft, 18-20 watt LED batten with 2000 lumen output and 2 year warranty	Each	19		
38	Supply, Installation, Testing and commissioning of 100% metal body Wall mounted Fan , 3/4 blade design, sweep 400-450 mm power input max 90 watt, Speed 1300-1330rpm with all accessories.	Each	7		
39	Ceiling Fan- Supply, Erecting, and testing of approved/specified make ceiling fans complete with down rod, canopy, blades and Electronic speed regulator 230-250 volts including connection with all necessary materials as required. Make- Usha/ Havells/Crompton	Each	2		
40	Supply & fixing of 230 mm exhaust fan 100% METAL body with all accessories etc. complete of make As specified in tender document or approved by concerned office in charge.	Each	4		
41	Wiring for computer networking from Jack Panel in data rack to computer workstation with Cat-6 computer cable in PVC conduits of size 20/ 25 mm including providing ferrules at both ends and termination at both ends including providing & fixing frame for Cat-6 with shutter, RJ 45 outlet, faceplate and mounting box complete of modular type, this work includes supply and laying of CAT-6 cable in PVC conduits throughout the length, from the I/O hub to the point.	Nos.	10		
42	Providing & fixing 9 U (Rack with glass door, opening in the front power panel 1 (horizontal), cable manager 1 lock & key) with switch.	Nos.	1		
43	Supply & fixing, Installation, Testing & Commissioning of 24 port Jack Panel.	Nos.	1		
44	Supplying and fixing Patch Cord-2 Meter- (DBPS Mounting Cord)	Nos.	10		
45	Supplying and fixing Patch Cord-1 Meter-	Nos.	10		
46	One call bell point with ceiling rose/ 6amp. 3 pin sockets controlled by one 6 amp. Push Modular switch. With call bell	Nos.	1		
47	Supplying , Installing Testing & Commissioning of LED Indicator (Red, Green & Yellow colour) for showing the Power ON/ Off position in Branch Light / Raw Power (1) , AC (1) , UPS OUT POWER SUPPLY (1). All indicators which needs to be off will be placed in one line and all indicator which needs to be off must be in other line . Marking of the Indicators to be done as per architect instructions.	Set	1		
48	Supply, Installation, Testing & Commissioning of 4 watt per meter (300 lumen per meter) LED TUBULAR cove Light with high efficiency electronic driver. (Make Philips)	MR	30		
49	SITC-Ceiling Profile Ligth Type TruGroove, Installation/ mounting type Recessed, Color Temperature Tc(K)3000/3500/4000 Housing (Material And Finish) Extruded aluminum trim and die-cast end plates, System Wattage 20W, C lassifications (IP/IK)IP20, 2" Inch Yellow Colour Cover (Glass/PC) Polycarbonate, Electrical Class II,/ LED Lamps 240 Nos/Mtr (LM26)5mtr roll with LED Driver lumens (Make IP Mac, Sanspa, Helius,)	RM	25		
GRAND TOTAL AMOUNT					
GST Extra					

APPROVED MAKE LIST

S.N.	DESCRIPTION	Approved Makes
S.N.	PVC Conduit	Precision/AKG /VIP
1	Ceiling Junction Boxes	Home lite/ANCHOR
2	Wires & cables	R.R./Havells/ Polycab
3	Modular Switches, Sockets etc	Crabtree / Northwest /Legrand
4	Lighting Fixtures	Philips/Lighting Tech. /Havells
5	M.C.B./RCCB/RCBO etc	Legrand/Havells/ HAGER
6	Distribution Boards	Same As Above
7	MCCB	Schneider/Legrand/Havells
8	Change Over Switches	A.B.B./Standard/ L.& T.
9	End Termination accessories	Dowells/Usha/Brecco/Cosmos
10	Telephone Cables & accessorieis	Havells, Krone, Finolex,
11	Fans/Exhaust fans	Crompton/Havell/USHA
12	Music Speakers	Philips/Bosch/Ahuja
13	Amplifiers	Philips/Bosch/Ahuja
14	DVR	Samsung, Honeywell , HIKVISION
15	Rg11, CAT5/CAT6 cables/Telephone wires	Legrand, Molex, D'Link, AMP
16	CCTV Dome Camera	Honywell, HIKVISION
17	Hard Disk drive	Seagate, HIKVISION
18	Smoke/Heat/Optical Fire Detectors	Edward, Siemens, Appolo Or other I.S.I.
19	Response Indicators, Hooters	Edward, Siemens OR other ISI Approved.

Place:

Date:

Signature of contractor with seal

BILL OF QUANTITY FOR ELECTRICAL WORK FOR PUNJAB & SIND BANK, RASDA BRANCH, UTTAR PRADESH.

ELECTRICAL WORKS (BRANCH + ATM)

S.No.	DESCRIPTION OF WORKS	UNIT	QTY	RATE	AMOUNT
1	<p>Light Primary Points in PVC Conduit - Point Wiring for light points, controlled through modular switches complete with PVC boxes & cover plate - The point wiring shall be done with 3x 1.5 sq.mm Fire Resistant Low smoke Low Halogen stranded Cu. Wire in PVC conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with PVC box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. Circuit wiring to be included in the point wiring rates. The circuit wiring starts from DB to point control box/ switch box using Fire Resistant Low smoke Low Halogen stranded Cu. Wire 2x2.5 sqmm & 1x2.5 sqmm earthing (min size) in 20/25/32 mm PVC conduit. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge</p>	Each	45		
2	<p>Light Secondary Points PVC Conduit - Point Wiring for light points interlooped from the primary point. The secondary point wiring shall be done with 3x 1.5 sq.mm FRLSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with MS box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge</p>	Each	25		
3	<p>5/6A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed /recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	12		
4	<p>5/6A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearby point through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No. 6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	3		

5	<p>UPS Primary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	10		
---	--	------	----	--	--

6	<p>UPS secondary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire looped from nearest UPS point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No., 6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	2		
7	<p>15/16A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No., 16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed /recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	8		
8	<p>15/16A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearest power point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No.,16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/ recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	2		
9	<p>AC point in PVC Conduit:- Supply & Installation of point wiring for Air Conditioner on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 20/25A , 3/5 pin sockets & 1 No. Single module 20/25A MCB, 1 Nos 25A Motor starter switch wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	6		
10	<p>Supply and laying 20 mm PVC conduit (MHS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.</p>	RM	30		

11	Supply and laying 25 mm PVC conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	35		
12	3x6 sq mm submains wiring in PVC conduit:- Supply and laying of 2x6 sq mm + 1x6 sq mm FR LSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	45		
13	Supply and laying of 3x10 submains wiring in PVC conduit Supply and laying of 2x10 sq mm + 1x10 sq mm FR (Fire Resistant) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	35		
14	Supply and laying of 4x10 flexible wire in PVC Conduit Supply and laying of 3x10 sq mm + 1x10 sq mm FR (Fire Resistant) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	15		
15	Supply installation testing and commissioning of 4 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with 2 Nos 63A DP MCB for Single Phase UPS input and output isolation	Set	3		
16	SITC of 12 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) i/c 1 Nos 63A DP MCB o/g 10 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	2		
17	SITC of 4 way Horizontal DB flush mounted on wall, sheet metal fabricated, powder coated, having dust- proof and vermin'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with i/c 1 Nos 63A TPN MCB o/g 12 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	3		
18	SITC of 4 way VTPN MCCB DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears (Double door VerticalL DB) with i/c 1 Nos 63A TPN MCCB Thermal Magnetic Release Adjustable overload: 0.8-1.0 x In Adjustable Short Circuit: 6-10 x In o/g 12 nos SP MCB (6-32A) 10 KA Breaking Capacity	Set	0		
19	SITC OF LT PANEL AS UNDER: (Manufacturrer must be approved from CPRI) Construction: Free Standing with front access, Dust & vermin Proof, Form 3b construction. Supply: 415V, 3Phase, 4 Wire, 50 Hz. Control Supply: 230V Single Phase Fault Level: 36KA for 1 Sec Fabrication: CRCA Sheet 14SWG for Gland Plate, Load Bearing Structure and Body, 16 SWG for partitions, doors and panels. 25x3 mm neoprene gasket for door, cover and gland plate. 40x5 mm gasket for joints and canopy. DC Locks to be provided on doors, danger plates on front and rear of bus bar chambers, live parts. Cable Entry / Exit : From top. Name plate: COPPER Powder Coating: Pre treated with 7 tank process and duly powder coated. TPN Busbars: 150A Rated copeer current density 1A/sq mm) with colour coded heat shrinkable sleeve. Neutral Bar of halfsize of Phase. Earth Bar of suitable size to be provided with earthing terminal on both ends Separate bus bar system to be provided for Emergency and Non Emergency supply outgoing Instrumentation: 1 Set 3 nos phase indicating lamps each backed up with MCB and switch shall be provided for each incomer. 1 no. VAF meter 0-200A with CT, selector switch, and fuse as reqd. Main Incomer- 125A MCCB Change Over - 1No. 100A Manual Changeover & 1 No. 63 A Automatic changeover for UPS Non Emergency Outgoing - 1 Nos 63A MCCB Emergency Outgoing 2 Nos 63A MCCB, 2 Nos 63A FP MCB, 4 Nos 40A DP MCB One Section in outgoing section in both emergency and non emergency section be kept spare for future provisions	Set	1		

20	SITC of 200Amp Kit kat Fuse unit 3 nos with 200 Amp neutral link on wooden board (3' x 3') complete with connections (new).	Set	1		
21	S & I of earth pit comprising of 600mm x 600mm 3mm. thick copper plate buried at a minimum depth of 2.7 meter including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	0		
22	S & I of earth pit comprising of G.I. earth pipe 4.5 metre long, 40 mm dia including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	3		
23	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required complete with insulation sleeve	RM	0		
24	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required complete with insulation sleeve	RM	0		
25	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface recessed conduit / submain wiring / cable as required.	RM	0		
26	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing along with existing surface / recessed conduit submain wiring / cable as required	RM	25		
27	Telephone point primary in PVC conduit: Supply & fixing on wall/ furniture/ partition recessed type modular telephone socket outlet (RJ-11) with mounting box & front plate complete with chase cutting, mending good etc. as required complete including Supply & laying of 1 pair 0.5 mm dia. PVC insulated unarmoured telephone cables through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement drawn from telephone tag block. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.	Each	3		
28	Providing, laying and connecting PVC insulated copper telephone cable of following sizes including termination in approved manner. 20-pair telephone cable.	RM	15		
29	Providing and fixing of telephone tag block (Krone type) of 50 pair housed in GI box with cover of suitable size including termination	Each	1		
30	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3x6 sq mm armoured aluminium cable in existing pipe / cable tray	RM	30		
31	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x50 armoured aluminium cable in existing pipe / cable tray	RM	45		
32	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x35 armoured aluminium cable in existing pipe / cable tray	RM	25		
33	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x70 aluminium armoured cable	SET	0		
34	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x50 aluminium armoured cable	SET	12		
35	Supply, Installation, testing and commissioning of 2'X2' Recessed type LED LIGHT FITTINGS of 33-36 W with minimum lumen level of 3900 lumens, CRCA / Extruded aluminium housing, efficiency of 120 lumens per watt and & Average life not less than 50000 hrs. The light should be hanged/supported by MS chain from ceiling directly and not be kept directly on false ceiling frame. Cutting of ceiling, framing etc. be included in the costs. Standard warranty of light fittings shall be minimum 2 years.	Each	11		
36	Supply, Installation, testing and commissioning of LED DOWNLIGHT FITTINGS of 15-18 W with minimum lumen level of 1650 lumens with die cast aluminium, efficiency of 110 lumens per watt and & Average life not less than 30000 hrs. Cutting of ceiling, modifications required to the ceiling be included in the cost. Standard warranty of light fittings shall be minimum 2 years.	Each	24		

37	Supply Installation testing and commissioning of 4 ft, 18-20 watt LED batten with 2000 lumen output and 2 year warranty	Each	19		
38	Supply, Installation, Testing and commissioning of 100% metal body Wall mounted Fan , 3/4 blade design, sweep 400-450 mm power input max 90 watt, Speed 1300-1330rpm with all accessories.	Each	7		
39	Ceiling Fan- Supply, Erecting, and testing of approved/specified make ceiling fans complete with down rod, canopy, blades and Electronic speed regulator 230-250 volts including connection with all necessary materials as required. Make- Usha/ Havells/Crompton	Each	2		
40	Supply & fixing of 230 mm exhaust fan 100% METAL body with all accessories etc. complete of make As specified in tender document or approved by concerned office in charge.	Each	4		
41	Wiring for computer networking from Jack Panel in data rack to computer workstation with Cat-6 computer cable in PVC conduits of size 20/ 25 mm including providing ferrules at both ends and termination at both ends including providing & fixing frame for Cat-6 with shutter, RJ 45 outlet, faceplate and mounting box complete of modular type, this work includes supply and laying of CAT-6 cable in PVC conduits throughout the length, from the I/O hub to the point.	Nos.	10		
42	Providing & fixing 9 U (Rack with glass door, opening in the front power panel 1 (horizontal), cable manager 1 lock & key) with switch.	Nos.	1		
43	Supply & fixing, Installation, Testing & Commissioning of 24 port Jack Panel.	Nos.	1		
44	Supplying and fixing Patch Cord-2 Meter- (DBPS Mounting Cord)	Nos.	10		
45	Supplying and fixing Patch Cord-1 Meter-	Nos.	10		
46	One call bell point with ceiling rose/ 6amp. 3 pin sockets controlled by one 6 amp. Push Modular switch. With call bell	Nos.	1		
47	Supplying , Installing Testing & Commissioning of LED Indicator (Red, Green & Yellow colour) for showing the Power ON/ Off position in Branch Light / Raw Power (1) , AC (1) , UPS OUT POWER SUPPLY (1). All indicators which needs to be off will be placed in one line and all indicator which needs to be off must be in other line . Marking of the Indicators to be done as per architect instructions.	Set	1		
48	Supply, Installation, Testing & Commissioning of 4 watt per meter (300 lumen per meter) LED TUBULAR cove Light with high efficiency electronic driver. (Make Philips)	MR	30		
49	SITC-Ceiling Profile Ligth Type TruGroove, Installation/ mounting type Recessed, Color Temperature Tc(K)3000/3500/4000 Housing (Material And Finish) Extruded aluminum trim and die-cast end plates, System Wattage 20W, C lassifications (IP/IK)IP20, 2" Inch Yellow Colour Cover (Glass/PC) Polycarbonate, Electrical Class II,/ LED Lamps 240 Nos/Mtr (LM26)5mtr roll with LED Driver lumens (Make IP Mac, Sanspa, Helius,)	RM	25		
GRAND TOTAL AMOUNT					
GST Extra					


APPROVED MAKE LIST

S.N.	DESCRIPTION	Approved Makes
S.N.	PVC Conduit	Precision/AKG /VIP
1	Ceiling Junction Boxes	Home lite/ANCHOR
2	Wires & cables	R.R./Havells/ Polycab
3	Modular Switches, Sockets etc	Crabtree / Northwest /Legrand
4	Lighting Fixtures	Philips/Lighting Tech. /Havells
5	M.C.B./RCCB/RCBO etc	Legrand/Havells/ HAGER
6	Distribution Boards	Same As Above
7	MCCB	Schneider/Legrand/Havells
8	Change Over Switches	A.B.B./Standard/ L.& T.
9	End Termination accessories	Dowells/Usha/Brecco/Cosmos
10	Telephone Cables & accessorieis	Havells, Krone, Finolex,
11	Fans/Exhaust fans	Crompton/Havell/USHA
12	Music Speakers	Philips/Bosch/Ahuja
13	Amplifiers	Philips/Bosch/Ahuja
14	DVR	Samsung, Honeywell , HIKVISION
15	Rg11, CAT5/CAT6 cables/Telephone wires	Legrand, Molex, D'Link, AMP
16	CCTV Dome Camera	Honywell, HIKVISION
17	Hard Disk drive	Seagate, HIKVISION
18	Smoke/Heat/Optical Fire Detectors	Edward, Siemens, Appolo Or other I.S.I.
19	Response Indicators, Hooters	Edward, Siemens OR other ISI Approved.


Place:

Date:

Signature of contractor with seal



PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH OFFICE - RASRA BALIA

CLIENT NAME & ADDRESS :

 Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :

 Ratwarbegpur, Near Pindra Railway Station, Varanasi-221206
 Ph:9899328602, 9997591118, vva.global@gmail.com

ARCHITECT:
Ar. Rahul Chaudhary


Partition
Civil Layout Plan

SHEET No	1
	1

DEALT : Sanjay Verma	CHECKED : Ar. Rahul Chaudhary
--------------------------------	---

SCALE : 1:100	DATE : 31March'2026
-------------------------	-------------------------------

DRAWING NO. : VA/BANK/PNS/RASRA/10.1	R1
--	-----------



FULL HEIGHT PARTITION WITH BOTH SIDE LAMINATES

LOW HEIGHT PARTITION WITH BOTH SIDE LAMINATES

WALL PANELLING FINISHING ARTIFICIAL GLASS WITH COVE

WALL PANELLING FINISHING WITH HDHMR AND ROYALE MATT FINISH

WALL PANELLING FINISHING LAMINATES

AREA STATEMENT	AREA
Strong Room Carpet Area	154.00 sq.ft.
Record Room Carpet Area	139.00 sq.ft.
Branch Hall Carpet Area	544.00 sq.ft.
Customer Lobby Carpet Area	258.00 sq.ft.
A.T.M. Carpet Area	39.00 sq.ft.
Pantry Carpet Area	38.00 sq.ft.
UPS Carpet Area	28.00 sq.ft.
Total Carpet Area	1200.00 sq.ft.
Total Carpet Area is 1200.00 sq.ft.	
Toilet Area	52.00 sq.ft.

PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH
CRUCIL, RAJRA BAZA

CLIENT NAME & ADDRESS :



Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :



Ratwarbeggur, Near Pindra Railway Station, Varanasi-221206
 Ph:9699328602, 9997391118, vva.global@gmail.com

ARCHITECT:
 Ar. Rahul Chaudhary


Partition
Interior Layout Plan

SHEET No
 1
 1

DEALT : Sanjay Verma
CHECKED : Ar. Rahul Chaudhary

SCALE : 1:100
DATE : 10March'2026

DRAWING NO. : WA/BANK/PNS/RASRA/10/1.1
R1



ELECTRICAL LEGENDS

DESCRIPTIONS	SYM	HGT
WALL FAN		6'-6"
TUBE LIGHT (LED)		8'-0" / ceiling
2'-0" X 2'-0" LIGHT (LED)		ceiling
CEILING FAN		ceiling
15 W DOWN LIGHTER (LED)		ceiling
AC POINTS		7'-0"
EXHAUST FAN		7'-0"

PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH OFFICE, RAJRA BAZAR

CLIENT NAME & ADDRESS :



Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :

VaASTU Vikalp Architects
 Ratwarbeggur, Near Pindra Railway Station, Varanasi-221206
 Ph:9899328402, 9997391118, vva.global@gmail.com

ARCHITECT:
 Ar. Rahul Chaudhary


Partiition **SHEET No**
1 / 1

FALSE CEILING & LIGHTING PLAN


DEALT : Sanjay Verma **CHECKED :** Ar. Rahul Chaudhary

SCALE : 1:100 **DATE :** 07 April'2026


DRAWING NO. : WA/BANK/PNS/RASRA/10/1.1 **R1**



FRONT ELEVATION



PLAN



CROSS SECTION OF VAULT- "B" CLASS

NOTE:

1. ALL DIMENSION AND BAR DIA IN mm.
2. THE MIX OF CONCRETE FOR ALL RCC WORK SHALL BE M25 (1:1:2)
3. Ø DENOTES TOR STEEL BARS CONFORMING TO IS:1786.
4. CLEAR COVER FOR REINFORCEMENT OF SLAB AND WALL SHALL BE 15MM.

APPROVED MAKE-

- 1- DESIGN MIX- ULTRATECH/ACC/ AMBUJA
- 2- CEMENT- ULTRATECH/ACC/ AMBUJA
- 3- REINFORCEMENT BAR- TATA/ SAIL/JINDAL-PANTHER

PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH OFFICE- RASRA BALLA

CLIENT NAME & ADDRESS :




Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :



Ratwarbegpur, Near Pindra Railway Station, Varanasi-221206
Ph:9899328602, 9997591118,
vva.global@gmail.com

ARCHITECT: Ar. Rahul Chaudhary		NORTH:	
DRAWING TITLE : STRONG ROOM DETAIL DRAWING			SHEET No 1 1
DEALT : Er. Sanjay Verma		CHECKED : Ar. Manoj Kumar	
SCALE : 1:65		DATE : 31 March '2026	
DRAWING NO. : WA/BANK/PSB/ID/10.2			OPTION/ REVISION



FULL HEIGHT PARTITION WITH BOTH SIDE LAMINATES

LOW HEIGHT PARTITION WITH BOTH SIDE LAMINATES

WALL PANNELLING FINISHING ARTIFICIAL GLASS WITH COVE

WALL PANNELLING FINISHING WITH HDHMR AND ROYALE MATT FINISH

WALL PANNELLING FINISHING LAMINATES

AREA STATEMENT	AREA
Strong Room Carpet Area	154.00 sq.ft.
Record Room Carpet Area	139.00 sq.ft.
Branch Hall Carpet Area	544.00 sq.ft.
Customer Lobby Carpet Area	258.00 sq.ft.
A.T.M. Carpet Area	39.00 sq.ft.
Pantry Carpet Area	38.00 sq.ft.
UPS Carpet Area	28.00 sq.ft.
Total Carpet Area	1200.00 sq.ft.
Total Carpet Area is 1200.00 sq.ft.	
Toilet Area	52.00 sq.ft.


PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH OFFICE,- RASRA BALIA

CLIENT NAME & ADDRESS :



Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :



Ratwarbegpur, Near Pindra Railway Station, Varanasi-221206
Ph:9899328602, 9997591118, vva.global@gmail.com

ARCHITECT:
Ar. Rahul Chaudhary


Partition
Interior Layout Plan

SHEET No
1
1

DEALT : Sanjay Verma
CHECKED : Ar. Rahul Chaudhary

SCALE : 1:100
DATE : 10March'2025

DRAWING NO. : WA/BANK/PNS/RASRA/ID/10.1
R1




ELECTRICAL LEGENDS

DESCRIPTIONS	SYM	HGT
WALL FAN		6'-6"
TUBE LIGHT (LED)		8'-0" / ceiling
2'-0" X 2'-0" LIGHT (LED)		ceiling
CEILING FAN		ceiling
15 W DOWN LIGHTER (LED)		ceiling
AC POINTS		7'-0"
EXHAUST FAN		7'-0"

PROJECT NAME:
FURNISHING WORKS & CIVIL WORKS FOR BRANCH OFFICE, RAJRA BAZAR

CLIENT NAME & ADDRESS :



Punjab & Sind Bank Zonal Office in Varanasi is located at 2nd Floor, SH-15/182-M-A-2, Airport Road, Shivpur, Varanasi, Uttar Pradesh, 221003

CONSULTANTS NAME & ADDRESS :

VaASTU Vikalp
 Architects

Ratwarbeggur, Near Pindra Railway Station, Varanasi-221206
 Ph:9899328402, 9997391118, vva.global@gmail.com

ARCHITECT:
 Ar. Rahul Chaudhary

Partiition **SHEET No**
1
1

AC LOCATION & VENTILATION PLAN

DEALT : Sanjay Verma **CHECKED :** Ar. Rahul Chaudhary

SCALE : 1:100 **DATE :** 07 April'2026

DRAWING NO. : WA/BANK/PNS/RASRA/10.1 **R1**